STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FURNISHED	REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																										
INT. #13 RAMP D STA. 0+220 RT	HANOVER NH 1	1	1800	300	0.54																																E-123
	MUSEUM OF SCIENCE	1	1800	300	0.54																																E-123
	NORWICH	1	1800	300	0.54						2			X																						E-123
INT. #13 RAMP D STA. 0+280 LT	WRONG WAY	1	900	600	0.54																														R5-1A		E-143
		1	600	600	0.36						1			X																					R9-4A		E-143
INT. #13 RAMP D STA 0+290 LT		1	600	750	0.45																														R4-7		E-144
		2	450	450	0.41						1			X																					OM1-1		E-150
INT. #13 RAMP D STA 0+290 RT	DO NOT ENTER	1	750	750	0.56						1			X																					R5-1		E-143
INT. #13 VT. RT. 10A MM. 0.382 RT	HANOVER NH 1	1	1800	300	0.54						2			X																								E-123
INT. #13 VT. RT. 10A MM. 0.352		1	600	750	0.45																														R4-7		E-144
		2	450	450	0.41						1			X																					OM1-1		E-150
INT. #13 VT. RT. 10A M.M. 0.286 LT		1	900	900	0.81						2			X																								E-152
INT. #13 VT. RT. 10A MM. 0.261 LT	NORWICH 1	1	1800	300	0.54																																E-123
	THETFORD 10	1	1800	300	0.54																																E-123
	ST JOHNSBURY 55	1	1800	230	0.54						2			X																								E-123
												m	m	m 48	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg									
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."	**TOTALS**				m2 7.77	m2	EA.	m2				m 48			m						kg			EA.	kg				EA.	EA.	kg						

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS05.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 136 OF 180

...\DGN\za046TS05.dgn 01/18/2006 11:08:12 AM