STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAMED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT. #14		1	600	300	0.18																												M3-2		E-136B
RAMP C	EAST TO WEST	1	600	300	0.18																												M4-5		E-136A
STA. 0+240 RT		1	600	300	0.18																												M3-4		E-136B
		1	750	600	0.45																														E-136B
	VERMONT 113 5 VERMONT 113	1	600	600	0.36																												M1-4		E-136A
		1	750	600	0.45																														E-136B
		1	525	375	0.20																												M5-1L		E-136B
		1	525	375	0.20						2													2	X							X	M5-1L E-123		E-136A
		1	525	375	0.20																												M5-1R		E-136B
INT. #14		1	1350	185	0.25																														E-133
RAMP C	2 GAS WRONG WAY																																		
STA. 0+360 RT		1	900	600	0.54																												R5-1A		E-143
	2 PHONE 2	1	1350	185	0.25																														E-133
	CAMPING 1	1	1350	185	0.25																														E-133
	2 FOOD	1	1350	185	0.25						2			X																					E-133
INT. #14 RAMP C STA. 0+300 RT	EAST THETFORD 1	1	1800	300	0.54																														E-123
	LYME NH 2	1	1800	300	0.54																														E-123
	THETFORD HILL 1	1	1800	300	0.54																														E-123
	CHELSEA 21	1	1800	300	0.54						2			X																					E-123
INT. #14 RAMP C STA. 0+360 LT	WRONG WAY	1	900	600	0.54																												R5-1A		E-143
		1	600	600	0.36						1			X																				R9-4A		E-143
												m	m	m 20.0	m	m	m		EA	kg	kg	kg		kg 90.4	kg	kg	kg								
TOTALS		m² 7.00	m²	EA.	m²							m 20.0			m					kg			EA. 2	kg 90.4				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS05.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:
PLOT DATE: 12/13/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 144 OF 180