STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
INT. #14 RAMP C END OF RAMP	STOP / DO NOT ENTER	2	750	750	1.13																												R1-1 RT & LT		E-143
		2	750	750	1.13																												R5-1 RT & LT		
	ONE WAY / ONE WAY	2	900	300	0.54						2			X																			R6-1L RT & LT		E-142
		2	900	300	0.54																												R6-1R RT & LT		
INT. #14 RAMP D STA. 0+030 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHHIKERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	900	900	0.81																												VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	900	900	0.81						2			X																			VR-002		E-142
INT. #14 RAMP D STA. 0+367 RT		1	750	750	0.81						1			X																			R3-2		E-143
INT. #14 RAMP D STA. 0+383 LT	ONE WAY	1	900	300	0.27						2		X																				R6-1R		E-142
INT. #14 SOUTHBOUND MM. 84.37		1	1200	1200	1.44						2			X																			W4-1R		E-150
INT. #14 VT. RT. 113 MM. 6.75 RT	JCT	1	525	375	0.20																												M2-1		E-135
	INTERSTATE 91	1	600	600	0.36						1			X																			M1-1		E-135
INT. #14 VT. RT. 113 MM. 6.88 RT		1	900	900	0.81						2			X																			W6-1		E-151
INT. #14 VT. RT. 113 MM. 6.90 MED		1	600	750	0.45																												R4-7		E-144
		2	450	450	0.41						1			X																			OM1-1		E-150
												m	m 8.0	m 44.0	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
	TOTALS				m² 9.71	m²	EA.	m²				m 52.0			m					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS05.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 12/13/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 145 OF 180