STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

METRIC Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT. #14 VT. RT. 113 MM. 6.89 LT	THETFORD HILL 1	1	1800	300	0.54																														E-123
	CHELSEA 21	1	1800	300	0.54						2			X																				E-123
INT. #14 VT. RT. 113 MM. 6.90 RT	EAST THETFORD 1	1	1800	300	0.54																														E-123
	LYME NH 2	1	1800	300	0.54																														E-123
	FAIRLEE 7	1	1800	300	0.54																														E-123
	ST JOHNSBURY 45	1	1800	300	0.54																														E-123
	NORWICH 9	1	1800	300	0.54						2												2	X											E-123
INT. #14 VT. RT. 113 MM. 6.93 RT	EAST NORTH SOUTH	1	600	300	0.18																													M3-2		E-136B
		1	600	300	0.18																													M3-1		E-135
		1	600	300	0.18																													M3-3		E-135
	VERMONT 113 INTERSTATE 91 INTERSTATE 91	1	750	600	0.45																															E-136B
		1	600	600	0.36																													M1-1		E-135
		1	600	600	0.36																													M1-1		E-135
		1	525	375	0.20																													M6-3		E-136B
		1	525	375	0.20						2												2	X									X	M6-3 E-123		E-135
		1	525	375	0.20																													M6-1		E-135
INT. #14 VT. RT. 113 MM. 6.93 LT	WEST	1	600	300	0.18																													M3-4		E-136B
	VERMONT 113	1	750	600	0.45						1			X																					E-136B
INT. #14 VT. RT. 113 MM. 6.94 MED		1	600	750	0.45																													R4-7		E-144
		1	600	600	0.36																													R3-2		E-143
		2	450	450	0.41						1			X																				OM1-1		E-150
	TOTALS				m² 7.94	m²	EA.	m²				m 16.0			m				EA	kg			EA. 4	kg 203.4				EA.	EA.	kg					
												m 16.0			m					kg				kg 203.4											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS05.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 12/13/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 146 OF 180