STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VTrans Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT. #14 VT. RT. 113 MM. 7.15 LT	WEST SOUTH NORTH	1	600	300	0.18																												M3-4		E-136B
		1	600	300	0.18																												M3-3		E-135
		1	600	300	0.18																												M3-1		E-135
	VERMONT 113 INTERSTATE 91 INTERSTATE 91	1	750	600	0.45																														E-136B
		1	600	600	0.36																												M1-1		E-135
		1	600	600	0.36																												M1-1		E-135
		1	525	375	0.20																												M6-3		E-136B
		1	525	375	0.20						2												2	X							X	M6-3		E-135
		1	525	375	0.20																												M6-1		E-135
INT. #14 VT. RT. 113 MM. 7.16 RT	EAST TO	1	600	300	0.18																												M3-2		E-136B
		1	600	300	0.18																												M4-5		E-136A
	VERMONT 113 5	1	750	600	0.45																														E-136B
											2												2	X							X			E-123
		1	600	600	0.36																												M1-4		E-136A
INT. #14 VT. RT. 113 MM. 7.16 MED		1	600	750	0.45																												R4-7		E-144
		2	450	450	0.41						1			X																		OM1-1		E-150
INT. #14 VT. RT. 113 MM. 7.18 LT	THETFORD HILL 1	1	1800	300	0.54																														E-123
	CHELSEA 21	1	1800	300	0.54																														E-123
	NORWICH 9	1	1800	300	0.54																														E-123
	FAIRLEE 7	1	1800	300	0.54																														E-123
	ST JOHNSBURY 45	1	1800	300	0.54						2												2	X											E-123
INT. #14 VT. RT. 113 MM. 7.19 RT	EAST THETFORD 1	1	1800	300	0.54																														E-123
	LYME NH 2	1	1800	300	0.54						2			X																					E-123
												m	m	m 12.0	m	m	m	EA	kg	kg	kg		kg 271.2	kg	kg	kg								
	TOTALS		m^2 8.12	m^2	EA.	m^2						m 12.0			m				kg			EA. 6	kg 271.2				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS05.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 12/13/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 148 OF 180