STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAMED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
INT. #15 RAMP B STA. 0+120 RT		1	900	900	0.81						2			X																			W3-1A		E-150
INT. #15 RAMP B STA. 0+180 RT	TO	1	600	300	0.18																												M4-5		E-136A
	5	1	600	600	0.36																												M1-4		E-136A
		1	525	375	0.20						1			X																			M6-1		E-136A
INT. #15 RAMP B STA. 0+260 RT	FOOD → WRONG WAY	1	1350	185	0.25																														E-133
		1	900	600	0.54																												R5-1A		E-143
	PHONE →	1	1350	185	0.25																														E-133
	GAS /24 HOUR 1 →	1	1350	185	0.25																														E-133
	← LODGING 2 →	1	1350	185	0.25																														E-133
	CAMPING 2 →	1	1350	185	0.25																														E-133
	← AMBULANCE	1	1350	185	0.25						2												2	X											E-133
INT. #15 RAMP B STA. 0+260 LT	WRONG WAY	1	900	600	0.54																												R5-1A		E-143
		1	600	600	0.36						1			X																			R9-4A		E-143
INT. #15 RAMP B STA. 0+220 RT	FAIRLEE 1 →	1	1800	300	0.54																														E-123
	ORFORD NH 1 →	1	1800	300	0.54																														E-123
	LAKE FAIRLEE 5 →	1	1800	300	0.54																														E-123
	← LAKE MOREY	1	1800	300	0.54						2			X																					E-123
												m 24			m					EA	kg				kg 90.4									
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."	**TOTALS**		m2 6.65	m2	EA.	m2						m 24			m					EA. 2	kg				kg 90.4				EA.	EA.	kg				

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS05.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 150 OF 180

...\DATA\za046TS05.dgn 01/18/2006 11:10:10 AM