STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT #15 F. ST. HWY. MM. 0.07 RT	THETFORD 7	1	1800	300	0.54																														E-123
	BRADFORD 6	1	1800	300	0.54																														E-123
	ST JOHNSBURY 37	1	1800	300	0.54						2			X																				E-123
INT #15 F. ST. HWY. MM. 0.09 RT	SOUTH NORTH	1 1	600 600	300 300	0.18 0.18																												M3-3 M3-1		E-135
	91 91	1 1	600 600	600 600	0.36 0.36																												M1-1 M1-1		E-135
		1 1	525 525	375 375	0.20 0.20						2												2	X							X	M5-1L M6-1		E-135
INT #15 F. ST. HWY. MM. 0.11 LT	NORTH	1	600	300	0.18																												M3-1		E-135
	91	1	600	600	0.36																												M1-1		E-135
		1	525	375	0.20						1			X																		M6-1		E-135
INT #15 F. ST. HWY. MM. 0.12 RT		1	900	900	0.81						2			X																		W4-2		E-151
	14' 1"	1	900	900	0.81						2			X																		W12-2		E-155
INT #15 F. ST. HWY. MM. 0.15 RT	SOUTH	1	600	300	0.18																												M3-3		E-135
	91	1	600	600	0.36																												M1-1		E-135
		1	525	375	0.20						1			X																		M6-1		E-135
	TOTALS				m² 6.20	m²	EA.	m²				m 32.0	m	m	m	m	m		EA	kg	kg	kg	EA. 2	kg 56.5	kg	kg	kg	EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS06.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 12/14/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 154 OF 180