STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAMED REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT #15 U.S. ROUTE 5 MM. 2.727 LT	SOUTH TO	1	600	300	0.18																												M3-3		E-136A
		1	600	300	0.18																												M4-5		E-135
	5 INTERSTATE 91	1	600	600	0.36																												M1-4		E-136A
		1	600	600	0.36																												M1-1		E-135
		1	525	375	0.20						2												2	X							X	M6-3		E-136A
		1	525	375	0.20																												M6-1		E-135
INT #15 U.S. ROUTE 5 MM. 2.727 RT	NORTH	1	600	300	0.18																												M3-1		E-136A
	5	1	600	600	0.36						1			X																		M1-4		E-136A
INT #15 U.S. ROUTE 5 MM. 2.764 LT	LAKE FAIRLEE 5	1	1800	300	0.54																														E-123
	NORWICH 14	1	1800	300	0.54						2			X																				E-123
INT #15 U.S. ROUTE 5 MM. 2.764 RT	ORFORD NH 1	1	1800	300	0.54																														E-123
	BRADFORD 7	1	1800	300	0.54						2			X																				E-123
INT. #16 RAMP A MM. 97.32		1	450	450	0.20						1	X																					0M1-1		E-150
INT. #16 RAMP A MM. 97.32	EXIT 16	1	1800	1500		2.70					2												2	X										E-131
INT. #16 RAMP A STA. 0+280 RT		1	900	900	0.81						2			X																		W3-1A		E-150
INT. #16 RAMP A STA. 0+340 RT	NORTH SOUTH TO	1	600	300	0.18																												M3-1		E-136B
		1	600	300	0.18																												M3-3		E-136B
		1	600	300	0.18																												M4-5		E-136A
	VERMONT 25 VERMONT 25 5	1	600	600	0.36																														E-136B
		1	600	600	0.36																														E-136B
		1	600	600	0.36																												M1-4		E-136A
		1	525	375	0.20																												M6-1		E-136B
		1	525	375	0.20						2												2	X							X	M6-1		E-136B
		1	525	375	0.20																												M6-1		E-136A
												m 2.0	m	m 28.0	m	m	m		EA	kg	kg	kg		kg 271.2	kg	kg	kg							
TOTALS			m² 7.41	m² 2.70	EA.	m²						m 30.0			m					kg			EA. 6	kg 271.2				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS06.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 156 OF 180

...\DGN\za046TS06.dgn 01/18/2006 11:11:18 AM