STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT. #16 RAMP A END OF RAMP	YIELD / DO NOT ENTER	2	900	900	1.62						2			X																				R1-2 LT & RT R5-1 LT & RT		E-146 E-143
INT. #16 RAMP B AT GORE		2	450	450	0.20						2	X																						OM1-1		E-150
INT. #16 RAMP B STA. 0+060 RT	YIELD	1	900	900	0.81						1			X																				R1-2		E-146
INT. #16 RAMP B STA. 0+080 RT	PROHIBITED PEDESTRIANS HITCHHIKING STOPPING FOR PASSENGERS BICYCLES FARM MACHINERY SNOW VEHICLES	1	900	900	0.81						2			X																				VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	900	900	0.81																													VR-002		E-142
INT. #16 RAMP B STA. 0+268 RT		1	750	750	0.81						1			X																				R3-2		E-143
INT. #16 RAMP B STA. 0+277 LT	ONE WAY	1	900	300	0.27						2		X																					R6-1R		E-142
INT. #16 SOUTHBOUND MM. 97.68		1	1200	1200	1.44						2			X																				W4-1R		E-150
INT. #16 SOUTHBOUND MM. 97.80	EXIT 35 M.P.H.	1	1200	1500	1.80						2												2	X									W13-2		E-150
INT. #16 RAMP C MM. 97.78		1	450	450	0.20						1	X																						OM1-1		E-150
INT. #16 RAMP C MM. 97.77	EXIT 16	1	1800	1500		2.70					2												2	X									W3-1A		E-131
INT. #16 RAMP C STA. 0+060 RT		1	900	900	0.81						2			X																						E-150
INT. #16 RAMP C STA. 0+100 RT	TO SOUTH NORTH	1	600	300	0.18																													M4-5		E-136A
		1	600	300	0.18																													M3-3		E-136B
		1	600	300	0.18																													M3-1		E-136B
	5 VERMONT 25 VERMONT 25	1	600	600	0.36																													M1-4		E-136A
		1	600	600	0.36																															E-136B
		1	600	600	0.36																															E-136B
		1	525	375	0.20																													M6-1		E-136A
		1	525	375	0.20						2												2	X								X	M6-1		E-136B
		1	525	375	0.20																													M6-1		E-136B
												m 6.0	m 8.0	m 40.0	m	m	m		EA	kg	kg	kg		kg 271.2	kg	kg	kg							
TOTALS					m² 12.93	m² 2.70	EA.	m²				m 54.0			m					kg			EA. 6		kg 271.2			EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS06.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 158 OF 180

...\SIGN\za046TS06.dgn 01/18/2006 11:11:53 AM