STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44	50	63 kg/m 3.4	3.9	5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75	100	100 MOD kg/m 1.9	2.5	2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75	89	100	125 kg/m 11.3	13.4	16.1	21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN PANEL REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																														
INT. #16 RAMP C STA. 0+200 RT	STATE POLICE 1 → WRONG WAY	1	1350	185	0.25																	1	1350	185	0.25																	E-133
		1	900	600	0.54																																			R5-1A		E-143
	← 1 FOOD	1	1350	185	0.25																																					E-133
	← 1 PHONE	1	1350	185	0.25																																					E-133
	← 1 DIESEL /24 HRS.	1	1350	185	0.25																																					E-133
	← 1 LODGING	1	1350	185	0.25						2			X																													E-133
INT. #16 RAMP C STA. 0+160 RT	← BRADFORD 2	1	1800	300	0.54																																					E-123
	← PIERMONT NH 4	1	1800	300	0.54																																					E-123
	BARRE 28 →	1	1800	300	0.54																																					E-123
	WAITS RIVER 12 →	1	1800	300	0.54						2			X																													E-123
INT. #16 RAMP C STA. 0+200 LT	WRONG WAY	1	900	600	0.54																																					
		1	600	600	0.36						1			X																													
INT. #16 RAMP C STA. 0+220 LT & RT	STOP DO NOT ENTER	2	750	750	1.13																																			R5-1 RT & LT		R-143
		2	750	750	1.13																																			R1-1 RT & LT		
	ONE WAY ONE WAY	2	900	300	0.54						2			X																											R6-1L RT & LT		R-142
		2	900	300	0.54																																			R6-1R RT & LT		
INT. #16 RAMP D STA. 0+030 RT	PROHIBITED PEDESTRIANS BICYCLES STOPPING FOR MOTORISTS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	900	900	0.81						2			X																											VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	900	900	0.81																																			VR-002		E-142
												m	m	m 36.0	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg												
	TOTALS				m² 11.13	m²	EA.	m²				m 36.0			m					kg			EA.	kg				EA.	EA.	kg									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS06.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:
PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 159 OF 180

...\GDN\za046TS06.dgn 01/18/2006 11:12:05 AM