STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT. #16 VT. ROUTE 25 MM. 0.972 LT	SOUTH TO	1	600	300	0.18																												M3-3		E-136B
		1	600	300	0.18																												M4-5		E-136A
	VERMONT 25 5	1	600	600	0.36						2			X																	X			E-136B
		1	600	600	0.36																												M1-4		E-136A
INT. #16 VT. ROUTE 25 MM. 0.972 RT	NORTH SOUTH NORTH	1	600	300	0.18																												M3-1		E-136B
		1	600	300	0.18																												M3-3		E-135
		1	600	300	0.18																												M3-1		E-135
	VERMONT 25 INTERSTATE 91 INTERSTATE 91	1	600	600	0.36																														E-136B
		1	600	600	0.36																												M1-1		E-135
		1	600	600	0.36																												M1-1		E-135
		1	525	375	0.20																												M6-3		E-136B
		1	525	375	0.20						2													2	X						X	M6-3		E-135
		1	525	375	0.20																												M6-1		E-135
INT. #16 VT. ROUTE 25 END OF MED. MM. 1.021		1	600	750	0.45																												R4-7		E-144
		1	600	600	0.36																												R3-2		E-143
		2	450	450	0.41						1			X																			0M1-1		E-150
INT. #16 VT. ROUTE 25 END OF MED. MM. 1.022		1	600	750	0.45																												R4-7		E-144
		1	600	600	0.36																												R3-1		E-143
		2	450	450	0.41						1			X																			0M1-1		E-150
INT. #16 VT. ROUTE 25 MM. 1.022 LT	NORTH	1	600	300	0.18																												M3-1		E-135
	INTERSTATE 91	1	600	600	0.36																												M1-1		E-135
		1	525	375	0.20						1			X																			M6-1		E-135
INT. #16 VT. ROUTE 25 MM. 1.030 RT	SOUTH	1	600	300	0.18																												M3-3		E-135
	INTERSTATE 91	1	600	600	0.36																												M1-1		E-135
		1	525	375	0.20						1			X																			M5-1L		E-135
INT. #16 VT. ROUTE 25 MM. 1.101 LT	NORTH INTERSTATE 91	1	600	300	0.18																												M3-3		E-135
		1	600	600	0.36																												M1-1		E-135
		1	525	375	0.20						1			X																			M5-1L		E-135
TOTALS		m² 7.96	m²	EA.	m²							m 28.0			m				EA	kg			EA. 2	kg 90.4				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS06.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:
PLOT DATE: 12/13/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 161 OF 180