STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT. #17 RAMP A STA. 0+200 RT	FOOD 3 / WRONG WAY	1	1350	185	0.25																														E-133
		1	900	600	0.54																												R5-1A		E-143
	PHONE 3	1	1350	185	0.25																														E-133
	GAS/DIESEL/24 HRS.	1	1350	185	0.25																														E-133
	LODGING 3	1	1350	185	0.25																														E-133
	HOSPITAL 5	1	1350	185	0.25																														E-133
	3 CAMPING 9	1	1350	185	0.25																														E-133
	INFORMATION 3	1	1350	185	0.25						2												2	X											E-133
INT. #17 RAMP A STA. 0+150 RT	SOUTH RYEGATE 4	1	1800	300	0.54																														E-123
	GROTON 7	1	1800	300	0.54																														E-123
	WELLS RIVER 3	1	1800	300	0.54																														E-123
	WOODSVILLE NH 5	1	1800	300	0.54						2			X																					E-123
INT. #17 RAMP A STA. 0+200 LT	WRONG WAY	1	900	600	0.54																												R5-1A		E-143
		1	600	600	0.36						1			X																		R9-4A		E-143
INT. #17 RAMP A END OF RAMP	STOP / DO NOT ENTER	2	750	750	1.13																												R1-1 RT & LT		E-143
		2	750	750	1.13																												R5-1 RT & LT		
	ONE WAY / ONE WAY	2	900	300	0.54						2			X																		R6-1L RT & LT		E-142
		2	900	300	0.54																												R6-1R RT & LT		
												m	m	m 20.0	m	m	m		EA	kg	kg	kg		kg 90.4	kg	kg	kg							
TOTALS					m² 8.69	m²	EA.	m²				m 20.0			m						kg			EA. 2	kg 90.4				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS06.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 12/13/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 164 OF 180