STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
INT. #17 RAMP B AT GORE		2	450	450	0.40						2	X																					OM1-1		E-150
INT. #17 RAMP B STA. 0+080 RT	YIELD	1	900	900	0.81						2			X																		R1-2		E-146
INT. #17 RAMP B STA. 0+100 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR PURPOSES OTHER THAN BICYCLES FARM MACHINERY SNOW VEHICLES	1	900	900	0.81						2			X																		VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	900	900	0.81																											VR-002		E-142
INT. #17 RAMP B STA. 0+322 RT		1	750	750	0.56						1			X																		R3-2		E-143
INT. #17 RAMP B STA. 0+338 LT	ONE WAY	1	900	300	0.27						2		X																			R6-1R		E-142
INT. #17 NORTHBOUND MM. 110.40		1	1200	1200	1.44						2			X																		W4-1R		E-150
INT. #17 RAMP C MM. 110.54	EXIT 35 M.P.H.	1	1200	1500	1.80						2												2	X								W13-2		E-150
INT. #17 RAMP C MM. 110.51		1	450	450	0.20						1	X																				OM1-1		E-150
INT. #17 RAMP C MM. 110.51	EXIT 17	1	1800	1500		2.70					2												2	X										E-131
INT. #17 RAMP C STA. 0+100 RT		1	900	900	0.81						2			X																		W3-1A		E-150
INT. #17 RAMP C STA. 0+140 RT	EAST TO WEST	1 1 1	600 600 600	300 300 300	0.18 0.18 0.18																											M3-2 M4-5 M3-4		E-136A
	302 5 302	1 1 1	750 600 750	600 600 600	0.45 0.36 0.45																											M1-4		E-136A
	← ← →	1 1 1	525 525 525	375 375 375	0.20 0.20 0.20						2												2	X							X	M6-1 M6-1 M6-1		E-136A
INT. #17 RAMP C STA. 0+240 LT	WRONG WAY	1	900	600	0.54																											R5-1A		E-143
		1	600	600	0.36						1			X																		R9-4A		E-143
												m 6	m 8.0	m 40.0	m	m	m		EA	kg	kg	kg		kg 271.2	kg	kg	kg								
TOTALS					m² 11.21	m² 2.70	EA.	m²				m 54			m					kg			EA. 6		kg 271.2			EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS06.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:
PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 165 OF 180

...\DGN\a046TS06.dgn 01/18/2006 11:12:33 AM