STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAMED REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT. #17 RAMP C STA. 0+240 RT	← 3 FOOD → WRONG WAY	1	1350	185	0.25																														E-133
		1	900	600	0.54																												R5-1A		E-143
	← 3 PHONE →	1	1350	185	0.25																														E-133
	← GAS/DIESEL/24 HRS →	1	1350	185	0.25																														E-133
	← 3 LODGING	1	1350	185	0.25																														E-133
	← 5 HOSPITAL	1	1350	185	0.25																														E-133
	← 9 CAMPING 3 →	1	1350	185	0.25																														E-133
	← 3 INFORMATION →	1	1350	185	0.25						2												2	X											E-133
INT. #17 RAMP C STA. 0+200 RT	← WELLS RIVER 3	1	1800	300	0.54																														E-123
	← WOODSVILLE NH 5	1	1800	300	0.54																														E-123
	SOUTH RYEGATE 4 →	1	1800	300	0.54																														E-123
	GROTON 7 →	1	1800	300	0.54						2			X																					E-123
INT. #17 RAMP C END OF RAMP	STOP / DO NOT ENTER	2	750	750	1.13																												R1-1		E-143
		2	750	750	1.13																												R5-1		
	ONE WAY / ONE WAY	2	900	300	0.54						2			X																		R6-1L RT & LT		E-142
		2	900	300	0.54																												R6-1R		
INT. #17 RAMP D AT GORE		2	450	450	0.20						2	X																					0M1-1		E-150
INT. #17 RAMP D STA. 0+20 LT	YIELD	1	900	900	0.81						2			X																		R1-2		E-146
												m 4.0	m	m 24.0	m	m	m		EA	kg	kg	kg		kg 124.3	kg	kg	kg							
	TOTALS				m² 8.80	m²	EA.	m²				m 28.0			m					kg			EA. 2	kg 124.3				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS06.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 01/18/2006
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 166 OF 180

...\SIGN\za046TS06.dgn 01/19/2006 11:12:46 AM