STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VTrans Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
INT. #17 RAMP D STA. 0+060 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR STORRIERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	900	900	0.81						2			X																				VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	900	900	0.81																													VR-002		E-142
INT. #17 RAMP D STA. 0+312 RT		1	750	750	0.56						1			X																				R3-2		E-143
INT. #17 RAMP D STA. 0+328 LT	ONE WAY	1	900	300	0.27						2		X																					R6-1R		E-142
INT. #17 SOUTHBOUND MM. 110.28		1	1200	1200	1.44						2			X																				W4-1R		E-150
INT. #17 U.S. RT 302 MM. 1.678 LT	SPEED LIMIT 50	1	600	750	0.45						1			X																				R2-1		E-142
INT. #17 U.S. RT 302 MM. 1.680 RT	JCT	1	525	375	0.20																													M2-1		E-135
	INTERSTATE 91	1	600	600	0.36						1			X																				M1-1		E-135
INT. #17 U.S. RT 302 MM. 1.700 RT		1	900	900	0.81						2			X																				W6-1		E-151
INT. #17 U.S. RT 302 MM. 1.718 RT	WELLS RIVER 3	1	1800	300	0.54																															E-123
	WOODSVILLE NH 5	1	1800	300	0.54																															E-123
	BARNET 11	1	1800	300	0.54																															E-123
	ST JOHNSBURY 22	1	1800	300	0.54																															E-123
	BRADFORD 13	1	1800	300	0.54																															E-123
	WHITE RIVER JCT 41	1	1800	300	0.54						2			X										2	X										E-123
INT. #17 U.S. RT 302 MM. 1.718 LT	SOUTH RYEGATE 4	1	1800	300	0.54																															E-123
	BARRE 28	1	1800	300	0.54						2			X																							E-123
												m	m 8.0	m 52.0	m	m	m		EA	kg	kg	kg		kg 90.4	kg	kg	kg								
	TOTALS				m² 10.03	m²	EA.	m²				m 60.0			m					kg			EA. 2	kg 90.4				EA.	EA.	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS06.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 12/13/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 167 OF 180