STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAMED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT. #17 U.S. RT 302 MM. 1.755		1	600	750	0.45																											R4-7		E-144
		2	450	450	0.41						1			X																		0M1-1		E-150
INT. #17 U.S. RT 302 MM. 1.755 LT	WEST	1	600	300	0.18																											M3-4		E-136A
	302	1	750	600	0.45						1			X																		M1-4		E-136A
INT. #17 U.S. RT 302 MM. 1.755 RT	EAST	1	600	300	0.18																											M3-2		E-136A
	NORTH	1	600	300	0.18																											M3-1		E-135
	SOUTH	1	600	300	0.18																											M3-3		E-135
	302	1	750	600	0.45																											M1-4		E-136A
	91	1	600	600	0.36																											M1-1		E-135
	91	1	600	600	0.36																											M1-1		E-135
		1	525	375	0.20																											M6-3		E-136A
		1	525	375	0.20						2												2	X						X	M6-3 E-123		E-135
		1	525	375	0.20																											M6-1		E-135
INT. #17 U.S. RT 302 END OF MED. MM. 1.767		1	600	750	0.45																											R4-7		E-144
		1	600	600	0.36																											R3-2		E-143
		2	450	450	0.41						1			X																		0M1-1		E-150
INT. #17 U.S. RT 302 END OF MED. MM. 1.777		1	600	750	0.45																											R4-7		E-144
		1	600	600	0.36																											R3-1		E-143
		2	450	450	0.41						1			X																		0M1-1		E-150
INT. #17 U.S. RT 302 MM. 1.778 LT	SOUTH	1	600	300	0.18																											M3-3		E-135
	91	1	600	600	0.36																											M1-1		E-135
		1	525	375	0.20						1			X																		M6-1		E-135
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."												m 20.0	m	m	m	m	m	EA	kg	kg	kg		kg 90.4	kg	kg	kg								
	TOTALS				m² 6.98	m²	EA.	m²				m 20.0			m				kg			EA. 2	kg 90.4				EA.	EA.	kg					

PROJECT NAME:	HARTFORD-NEWBURY
PROJECT NUMBER:	IM 091-2(69)
FILE NAME: ...\zg046TS06.dgn	PLOT DATE: 12/13/2005
PROJECT LEADER: J. W TUCKER	DRAWN BY: S. J BIJOLLE
DESIGNED BY:	CHECKED BY: J.D. AUSTIN
	SHEET 168 OF 180