STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

NOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAMED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
INT. #17 U.S. RT 302 MM. 1.812 LT	GROTON 7	1	1800	300	0.54																														E-123
	BARRE 28	1	1800	300	0.54																														E-123
	BRADFORD 13	1	1800	300	0.54																														E-123
	WHITE RIVER JCT 41	1	1800	300	0.54						2			X																					E-123
INT. #17 U.S. RT 302	91 NORTH ST JOHNSBURY LEFT LANE / EAST 302	1 1	3960 1830	2740 2740		10.85 5.01																											MOUNT ON OVERHEAD STRUCTURE	77	E-135 E-136A
INT. #17 U.S. RT 302	91 SOUTH WHITE RIVER JCT LEFT LANE / WEST 302	1 1	4115 1830	2740 2740		11.28 5.01																											MOUNT ON OVERHEAD STRUCTURE	77	E-135 E-136A
INT. #17 U.S. RT 302 MM. 1.846 LT	LEFT LANE MUST TURN LEFT	1	750	750	0.56						1			X																			R3-7L		E-140
INT. #17 U.S. RT 302 MM. 1.957 MM. 1.962		2	600	750	0.90																												R4-7		E-144
		4	450	450	0.81						2			X																			0M1-1		E-150
INT. #17 U.S. RT 302 MM. 1.958 RT	NORTH	1	600	300	0.18																												M3-1		E-135
	91	1	600	600	0.36																												M1-1		E-135
		1	525	375	0.20						1			X																			M6-1		E-135
INT. #17 U.S. RT 302 END OF MED. MM. 1.977		1 1	600 600	750 600	0.45 0.36																												R4-7 R3-1		E-144 E-143
		2	450	450	0.41						1			X																			0M1-1		E-150
												m 28.0	m	m	m	m	m	EA	kg	kg	kg		kg	kg	kg	kg								
	TOTALS				m² 6.39	m² 32.15	EA.	m²				m 28.0			m				kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S 'SIGN POST DESIGN GUIDELINE.'

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS06.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 12/13/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 169 OF 180