STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS KG	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
INT. #17		1	600	300	0.18																											M3-4		E-136A
U.S. RT 302	WEST SOUTH NORTH	1	600	300	0.18																											M3-3		E-135
MM. 1.982 LT		1	600	300	0.18																											M3-1		E-135
	302 INTERSTATE 91 INTERSTATE 91	1	750	600	0.45																											M1-4		E-136A
		1	600	600	0.36																											M1-1		E-135
		1	600	600	0.36																											M1-1		E-135
		1	525	375	0.20																											M6-3		E-136A
		1	525	375	0.20						2												2	X							X	M6-3 E-123		E-135
		1	525	375	0.20																											M6-2		E-135
INT. #17 U.S. RT 302 END OF MED. MM. 1.982		1	600	750	0.45																											R4-7		E-144
		1	600	600	0.36																											R3-2		E-143
		2	450	450	0.41						1			X																	0M1-1		E-150
INT. #17 U.S. RT 302 MM. 2.015 RT	EAST	1	600	300	0.18																											M3-2		E-136A
	302	1	750	600	0.45						1			X																	M1-4		E-136A
INT. #17 U.S. RT 302 END OF MED. MM. 2.015 MM. 2.017		3	600	750	1.35																											R4-7		E-144
MM. 2.019		6	450	450	1.22						3			X																	0M1-1		E-150
INT. #17 U.S. RT 302 MM. 2.019 LT	SOUTH RYEGATE 4	1	1800	300	0.54																														E-123
	BARRE 28	1	1800	300	0.54																														E-123
	BRADFORD 13	1	1800	300	0.54																														E-123
	WHITE RIVER JCT 41	1	1800	300	0.54																														E-123
	BARNET 11	1	1800	300	0.54																														E-123
	ST JOHNSBURY 22	1	1800	300	0.54						2			X																					E-123
												m	m	m 28.0	m	m	m		EA	kg	kg	kg		kg 90.4	kg	kg	kg							
	TOTALS		m^2 9.97	m^2	EA.	m^2						m 28.0			m					kg			EA. 2	kg 90.4				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD-NEWBURY
PROJECT NUMBER: IM 091-2(69)

FILE NAME: ...\za046TS06.dgn
PROJECT LEADER: J. W TUCKER
DESIGNED BY:

PLOT DATE: 12/13/2005
DRAWN BY: S. J BIJOLLE
CHECKED BY: J.D. AUSTIN
SHEET 170 OF 180