STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

				EMPLOYEE TRAINEE SHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						63	63	EA	TRAILING END TERMINAL	621.52	0
						72	72	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	0
						39	39	EA	GUARDRAIL APPROACH SECTION, TYPE I	621.70	0
						100	100	M	REMOVING AND RESET GUARDRAIL	621.75	EST
						2000	2000	EA	REPLACE GUARDRAIL POST ASSEMBLY	621.76	EST
						1000	1000	EA	REPLACE GUARDRAIL BEAM UNIT	621.77	EST
						9 400	9 400	M	REMOVAL & DISPOSAL OF GUARDRAIL	621.80	21
						2310	2310	HR	UNIFORMED TRAFFIC OFFICERS	630.10	23
						3465	3465	HR	FLAGGERS	630.15	35
						1	1	LS	FIELD OFFICE - ENGINEERS	631.10	-
						1	1	LS	TESTING EQUIPMENT - BITUMINOUS (MOD.)	631.17	-
						1	1	LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	-
				2080			2080	HR	EMPLOYEE TRAINEESHIP	634.10	0
						1	1	LS	MOBILIZATION	635.10	-
						1	1	LS	TRAFFIC CONTROL	641.10	0
						7	7	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	0
						635	635	M	DURABLE 100 mm WHITE LINE (THERMOPLASTIC)	646.40	10
						225	225	M	DURABLE 100 mm YELLOW LINE (THERMOPLASTIC)	646.41	4
						50 250	50 250	M	DURABLE 150 mm WHITE LINE (THERMOPLASTIC)	646.414	500
						40 205	40 205	M	DURABLE 150 mm YELLOW LINE (THERMOPLASTIC)	646.415	399
						900	900	M	DURABLE 300 mm WHITE LINE (THERMOPLASTIC)	646.44	10
						40	40	M	DURABLE 600 mm STOP BAR (THERMOPLASTIC)	646.46	1
						46	46	EA	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50	0
						635	635	M	TEMPORARY 100 mm WHITE LINE	646.60	10
						225	225	M	TEMPORARY 100 mm YELLOW LINE	646.61	4
						100 500	100 500	M	TEMPORARY 150 mm WHITE LINE	646.614	1000
						280	280	M	TEMPORARY 150 mm WHITE LINE (TYPE II TAPE)	646.614	10
						80 410	80 410	M	TEMPORARY 150 mm YELLOW LINE	646.615	798
						1800	1800	M	TEMPORARY 300 mm WHITE LINE	646.64	20
						110	110	M	TEMPORARY 300 mm WHITE LINE (TYPE II TAPE)	646.64	10

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT : BRATTLEBORO - ROCKINGHAM

PROJECT NO.: IM 091-1(39)

DESIGN FILE NAME: _/pave/99a202/pa202.dgn
IPARM FILE NAME: pa202gs02.i
PLOT DATE: 02-JUN-2005_14
SURVEYED BY: CLD ENGINEERS INC
SURVEY DATE: 10/00
SQUAD LEADER: WRH
DRAWN BY: MPS
SHEET: 8 OF 37