PARCEL	INSTRUMENT	DATE	GRANTOR	GRANTEE	RECORDED BOOK	RECORDED PAGE	RECORDED DATE	REMARKS CUL STA
A-B	Q.C.D.	8-24-37	J.C. & M.L. ZOTTMAN	STATE OF VT.	7	42	8-26-37	6+03
A'	Q.C.D.	8-5-37	HAPVINE TEA ROOM INC.	"	7	38	8-7-37	
A''	Q.C.D.	8-2-37	MYRON VESPER	"	7	37	8-7-37	
A'''	Q.C.D.	5-7-38	MYRON VESPER	"	7	49	5-9-38	

ESTIMATE OF QUANTITIES FOR BRIDGE			
15	Channel Excavation	Cu. Yds.	778
16	Structure Excavation	" "	547
41A	Concrete Class "A"	" "	438
41C	Concrete Class "C"	" "	39
42	Reinforcing Steel	Lbs.	6381
43B	Steel Superstructure	L.S.	1
56	Temporary Bridge	"	1
57	Removal of Present Superstructure	"	1
65	Timber Piling	L.F.	1790
68	Rip Rap for bank protection (Heavy Type)	Cu. Yd.	556
80A	Cable Guard Rail	L.F.	296

BRIDGE DATA	
PRESENT	PROPOSED
Wood Truss	Type: I Beam
47'	Spans: 40-59-49
23'	Clear Hwy: 30' Min.
1000 #'	Wgt. Except: 2350 #'
62'	Length: 148'
18'	Road Width: 24'

BM #2A Spike in Root 18" Elm 22' Lt Sta 9+00 Elev. 69.44