



BRIDGE DATA		
	PRESENT	PROPOSED
TYPE	PLANK-SPAWN ARCH	I-BEAM CONC. ARCH
SPAN OVERALL	25'-0"	66'-0"
CLEAR HEIGHT	6'-0"	9'-0"
WIDEWAY	72'-0"	33'-0"
ROADWAY WIDTH	71'-0"	34'-0"
SPAN CLEAR	26'-0"	36'-0"

SUMMARY OF QUANTITIES (BRIDGE ONLY)

QUANTITY	UNIT	ITEM	NO.
400	cu yd	Channel Excavation	15
45	cu yd	Structure Excavation	16
1	L.S.	Maintenance of Traffic	1B
90	cu yd	Concrete Class A	11A
17,980	Lb.	Reinforcing Steel	12
1	L.S.	Steel Superstructure (48,400')	13B
1	L.S.	Removal of Present Superstructure	57
300	cu yd	Riprap for Bank Protection (heavy type)	68-B
120	lin ft	Cable Guard Rail	80A

*Handwritten note: mp 4.68*

