

Plan No. 24-P
 Scale: 1" = 40'

Sheet No. 7
 FLOOD BRIDGE No. 24-P



Bridge Data	
TYPE	SPAN
SPAN	235' 0"
CLEAR HEIGHT	45' 0"
PIERS	3
ROADWAY WIDTH	70' 0"
SKINNING	28' 0"

SUMMARY OF QUANTITIES (BRIDGE ONLY)		
QUANTITY	UNIT	ITEM
400	cu yd	Channel Excavation
15	cu yd	Structure Excavation
1	LS	Maintenance of Traffic
90	cu yd	Concrete Class A
17,380	lb	Reinforcing Steel
1	LS	Steel Superstructure (40,400')
1	LS	Removal of Present Superstructure
300	cu yd	Sub-base for 4" Bit. Preliminary
128	lin ft	Cable Guard Rail

Station	Notes
Sta 7+00	12' Sub-base of Gravel
Sta 11+25	12' Sub-base of Gravel
Sta 11+25	END OF PROJECT FLOOD BRIDGE No. 24-P

HALL'S
 ROAD & RAIL
 SHEET 24-P

SCALE: 1" = 40'