

FED. ROAD DIST. NO.	FED. AID FISCAL YEAR	SHEET NO.	TOTAL SHEETS
17	1923	13	39

GUARD RAIL REQUIRED ON LEFT

Sta. 164+50 to Sta. 166+10 - 160 Ft.
 " 167+88 " " 168+12 - 24 "
 " 171+00 " " 171+48 - 48 "
 " 173+00 " " 174+60 - 160 "
 " 176+17 " " 176+41 - 24 "

ON RIGHT

Sta. 165+72 to Sta. 165+96 - 24 Ft.
 " 167+88 " " 168+12 - 24 "
 " 171+00 " " 171+24 - 24 "
 " 176+71 " " 176+41 - 24 "
 " 178+18 " " 178+42 - 24 "
 " 178+88 " " 179+12 - 24 "

This Sheet - Total - 560 Ft.

NEW CULVERTS REQUIRED

Sta. 165+83 - 16" Corr. Iron Pipe Culvert - 34 Ft. Long
 1-2 1/2 - 5 Concrete - 1.7 Cu. yds.
 Sta. 168+00 - 14" Corr. Iron Pipe Culvert - 32 Ft. Long
 1-2 1/2 - 5 Concrete - 1.7 Cu. yds.
 Sta. 170+29 - 14" Corr. Iron Pipe Culvert - 24 Ft. Long
 1-2 1/2 - 5 Concrete - 1.7 Cu. yds.
 Sta. 172+70 - 14" Corr. Iron Pipe Culvert - 34 Ft. Long
 1-2 1/2 - 5 Concrete - 1.7 Cu. yds.
 Sta. 175+30 - 16" Corr. Iron Pipe Culvert - 34 Ft. Long
 1-2 1/2 - 5 Concrete - 1.7 Cu. yds.
 Sta. 177+00 - 3 1/2 - 3 Rein. Conc. Culvert - 30 Ft. Long
 1-2 - 4 Concrete - 4 Cu. yds.
 1-2 1/2 - 5 Concrete - 12.5 Cu. yds.
 Reinforcing Steel - 200 lbs.

