



CONSTRUCT DRIVE Lt 68+02 Rt 70+20
 GRADING Lt 72+20-73+00 Rt
 THREE CABLE GUARD RAIL WITH STEEL POSTS Lt 72+00-72+52 Rt 55+00-73+00
 DRILLING AND BLASTING OF SOLID ROCK SUBGRADE Lt 66+75-68+60 Rt 72+16
 UNCLASSIFIED CHANNEL EXCAVATION Lt 66+25-73+00 Rt

CURVE DATA
 Δ 14° 11' Lt
 D 2° 30'
 R 2251.6
 T 269.1
 L 367.8
 E 17.7
 Bank 1/2" per ft

REMOVAL AND DISPOSAL OF PRESENT GUARD RAIL Lt 59+00-59+76 Rt 66+25-68+16
 Lt 69+63-72+33 Rt

CURVE DATA
 Δ 15° 51' Lt
 D 1° 45'
 R 3274.0
 T 543.5
 L 1077.2
 E 34.8
 Bank 1/2" per ft

STONE FILL (HEAVY TYPE) Lt 66+25-73+00 Rt
 12" BLANKET OF GRAVEL BACKFILL Lt 66+25-73+00 Rt
 DEMOLITION AND DISPOSAL OF BUILDING Lt 67+40(1) Rt

SECTION I
 BEGIN RELINQUISHMENT
 STA. 70+25 60' LT.

BM #5
 SLP 36" Oak
 U.S. Elev. 226.91

PI 64+69.4
 64+66.5
 POST 64+07.0
 67+00 Lt 4" V.C.P. 70' Lt
 Retain & Extend with New 4" V.C.P.
 68+82 Lt
 New 12" V.C.P. 60' Lt
 68+82 Lt
 Retain & Extend with New 4" V.C.P.

REMOVE
 70+11 Lt 12" ACCGMP 74' Rt
 REMOVE
 70+90 Lt 12" V.C.P. 73' Rt
 RETAIN

WEST RIVER



BRATTLEBORO-DUMMERSTON
 Project No. 0119(1)
 Sheet 58A of 125 Sheets