



STA 928+00 - 930+40
 Sod to be removed
 and spread on cut slopes
 in this same area to be paid
 for as common Excavation Item 10-11

PARCEL	INSTRUMENT	DATE	GRANTOR	GRANTEE	RECORDED	REMARK
D.E.F.	W.D.O.E.	12-5-60	P.B. & MILDRED STEPHENSON	ST. OF RT.	BOOK 20	PAGE DATE 320-1 12-28-60
A	W.D.O.E.	12-5-60	JEAN & ANNETTE FAUCHER	ST. OF RT.	BOOK 20	PAGE DATE 330 12-28-60 E. CULV.

Note -
 The Contractor will be required to remove the Excavation to the limits of the neat lines as shown on the plans etc. from Sta. 932+50 and ahead to the extent of removing 24276 cu yds of excavation and this excavation shall be used in embankments on project F.A.P. 79-E(1) from Sta. 797+00± to Sta. 924+00.
 The Contractor will not be required to make embankments or place any drainage or sub-base through the section from Sta. 924+00 to Sta. 946+00.

Note - Sta. 933+50± to 938+50±
 The area between the new location and the old road shall be levelled as shown by the Cross-sections. The material removed shall be used in the construction of embankments.

Sta 932+75 to Sta 933+50
 Surface to be carried from
 paved gutter to paved gutter

BM #94 Spot on Boulder 9' Lt. Sta. 922+00 Elev. 854.80
 BM #95 Spike in Root of 20' Elm 65' Rt. Sta. 929+40 Elev. 894.42

SERIES F.A.P. NO. 79-E(1)
 SHEET 20 OF 102