



SCALES
 PLAN 1" = 50'
 HOPE 1" = 20'
 TYPICAL SECT. VERT. 1" = 10'

SUMMARY OF QUANTITIES -
 ITEM 14 - CHANNEL EXCAVATION 2,545 cu yds
 OVERSLOW 435 "
 TOTAL 3,000 cu yds

NOTE:
 1. DISPOSAL OF CHANNEL EXCAVATION. The material removed as an excavation in the widening of the Mississippi River as shown on layout sheets #10 and cross section sheets #35-43 shall be wasted or deposited on the west side of the channel widening on disposal areas acquired by Albert Roberge as shown on the plans, said material to be deposited in a workmanlike manner and to the satisfaction of the Engineer. An under or wood that is necessary to cut in the channel right-of-way shall be piled in a convenient place for removal by proper purposes from the River adjoining to this location has been shown on the State, one on the South and then the pasture of Albert Roberge approximately as shown on layout sheet #10, one on the North end of the field next to the fence dividing the property of Albert Roberge and Victor Descheneau as shown sheet #10.
 The contractor shall be held liable for any damage from blasting and construction operations. The fields cleared of loose blasted stone by the contractor.

PARCEL	INSTRUMENT	DATE	GRANTOR	GRANTEE	RECORDED	REMARKS
	A-D	10-20-35	VICTOR DESCHENEAU	STATE	29	513 10-31-35
	A'	11-7-35	ALBERT ROBERGE	"	29	570 11-9-35

BM #1
 10" SPRUCE 26 FEET OF STA. 3+05 ELEV. 751.56
 SPOT ON LEDGE 173 FT. OF STA. 7+60 ELEV. 748.81