

WOOD GUARD RAIL REQUIRED

STA. 0+67 TO STA. 1+23 - LENGTH 56 feet
4+06 " 4+70 " 24 "
5+37 " 6+01 " 24 "
6+71 " 7+35 " 24 "
8+06 " 8+70 " 24 "
9+41 " 10+05 " 24 "
11+12 " 11+76 " 24 "
12+51 " 13+15 " 24 "
TOTAL FOR SHEET - 360 feet

CABLE GUARD RAIL REQUIRED

LEFT

STA. 9+80 TO STA. 13+00 - LENGTH 320 ft.

NEW CULVERT REQUIRED

STA. 0+75 - 24" REINF. CONCRETE PIPE 30' LONG
Concrete Class B (1-2 1/2") - 4.1 cu yds
Reinforcing Steel - 33 lbs
STA. 4+10 - 15" REINF. CONCRETE PIPE - 36' LONG
Concrete Class B (1-2 1/2") - 1.9 cu yds
Reinforcing Steel - 33 lbs
STA. 6+53 - 36" REINF. CONC. BOX CULVERT
Concrete Class A (1-2 1/2") - 17.8 cu yds
Reinforcing Steel - 1190 lbs
STA. 8+50 - 10" REINF. CONCRETE PIPE 30' LONG
Concrete Class B (1-2 1/2") - 2.7 cu yds
Reinforcing Steel - 33 lbs

STA. 11+00 - 18" REINF. CONCRETE PIPE 36' LONG
Concrete Class B (1-2 1/2") - 2.7 cu yds
Reinforcing Steel - 33 lbs
STA. 12+64 - 10" REINF. CONCRETE PIPE - 42' LONG
Concrete Class B (1-2 1/2") - 2.7 cu yds
Reinforcing Steel - 33 lbs

