


HERBERT E. AND ELEANORE J. CLARK


LIST OF QUANTITIES (BRIDGE ONLY)

ITEM NO	DESCRIPTION	UNIT	QTY	UNIT PRICE	TOTAL	ITEM NO	DESCRIPTION	UNIT	QTY	UNIT PRICE	TOTAL
102-A	BORROW (MODIFIED)	CY	7000	60K	420,000	504	STEEL PILING	LF	1080	1080	1,188,000
103-A	TRENCH EXCAVATION OF EARTH	CY	180	18A	3,240	504-1	CUT OFF FOR STEEL PILING	LF	54	54	594
104	CHANNEL EXCAVATION	CY	195	195B	38,025	505	STANDARD STRUCTURAL TIMBER (MODIFIED)	MBM	16	16	160
105	STRUCTURE EXCAVATION	CY	195	195C	38,025	506	PIPPAP FOR BANK PROTECTION	CY	1802	1802	180,200
106	MAINTENANCE OF TRAFFIC FOR BRIDGE PROJECT	LS	1	1	1	507	ELECTRICAL EQUIPMENT	LS	1	1	1
201-A	SUB-BASE OF GRAVEL (MEASURED IN PLACE)	CY	100	6	600	508-A	DEMOLITION & REMOVAL OF BLDGS	LS	1	1	1
401-A	CONCRETE - CLASS A	CY	5	5	25	509	MACHINERY	LS	1	1	1
401-B	CONCRETE - CLASS B	CY	2455	2308	566,410	510	CONTROL HOUSE	LS	1	1	1
402	REINFORCING STEEL	LBS	11,700	37.60	439,920	511	OPERATOR HOUSE	LS	1	1	1
403-A	STRUCTURAL STEEL	LBS	3100	0	3100						
403-B	STEEL SUPERSTRUCTURE	LS	1	1	1						
406	5" STEEL GRID FLOORING	SF	4370	4570	199,700						
406	4" STEEL GRID FLOORING	SF	1200	1200	144,000						
406	1 1/2" STEEL GRID FLOORING	SF	144	144	20,736						
407-A	STEEL PUNCHINGS	LBS	340,000	340,000	115,600,000						
407-B	BILLET STEEL FOR COUNTERWEIGHTS	LBS	350,000	350,000	122,500,000						
442	REMOVAL OF PRESENT SUPERSTRUCTURE	LS	1	1	1						
501	REMOVING EQUIPMENT FOR DRIVING PILES	LS	1	1	1						
501	BITUMINOUS CONCRETE PAVEMENT FOR BRIDGE FLOORS	TONS	42	42	1,764						



GENERAL OPERATING PROCEDURE
 The operation shall be controlled from the control house on the right of Pier #2 and shall be interlocked for the following procedure in raising:
 The flashing red lights on all posts shall go together with the warning bells. A time interval of 45 sec shall elapse before the gates start to lower. The flashing red lights on gate arms shall go on when gate starts to lower. A time interval of 30 sec shall elapse from start of lowering of gate to start of the movement to with draw center lock pins. After the center lock shear pins are with drawn the bascule spans are raised.
 The reverse procedure shall be followed in closing the bridge.

- LAKE CHAMPLAIN**
- This portion of tender pier to be removed to lake bottom before any other work is started to allow for laying of submarine cables by the Telephone & Utility Company.
- LIST OF SHEETS (BRIDGE ONLY)**
- 11 OF 12 GENERAL PLAN & PROFILE
 - 12 PLAN & ELEVATION OF BRIDGE
 - 13 DETAILS OF ABUTMENT
 - 14 PLAN & ELEVATION OF PIERS
 - 15 SECTION & ELEVATION OF PIERS
 - 16 CONTROL HOUSE & LADDERS
 - 17 MATERIAL LIST & NOTES - PIERS
 - 18 DETAILS OF APPROACH SEAS
 - 19 PLAN OF BASCULE & TRUNION GIRDERS
 - 20 DETAILS OF BASCULE GIRDER
 - 21 DETAILS OF TRUNION GIRDER
 - 22 DETAILS OF BREAK IN SHK & BRIDGE FLOOR
 - 23 DETAILS OF PIN
 - 24 STEEL PLAN AT CENTER
 - 25 DETAILS OF BEARING PEDESTALS
 - 26 LAYOUT OF MACHINERY
 - 27 LAYOUT OF HAND OPERATED MACHINERY
 - 28 LAYOUT OF CENTER LOCK MECHANISM
 - 29 DETAILS OF NAVIGATION LIGHTS
 - 30 DETAILS OF WARNING GATES
 - 31 WORKS DISSEM
 - 32-34 SPECIFICATIONS OF ELEC EQUIPMENT & OPERATORS HG. 130
 - 35 DETAILS OF OPERATOR HOUSE
 - 36 LAYOUT OF WATER SUPPLY & SANITARY SERVICES OPERATOR HOUSE
 - 37 OPERATORS SLEEPING QUARTERS
 - 38-43 STD 38-30 DETAIL BEARING DEVICES
 - 38-43 CHANNEL SECTIONS



3-29
 3-29
 3-29

3-29
 3-29

BM # 2 30' E 107.48
 BM # 2 30' E 107.48
 BM # 2 30' E 107.48

June 1, 1980 - Revised in accordance with
 O.P.R. letter of May 28, 1980.

GRAND ISLE - NORTH HERO DRAWBRIDGE
 Sheet 11 of 12