



PLANK GUARD RAIL ITEM 540	
STATION	POS
EASTBOUND	
1195+50	EA
WESTBOUND	
1197+75	EA

Two Cable Guard Rail  
S.A.#2 714+69-714+93 Lt.  
S.A.#3 714+63-715+00 Rt.  
S.A.#1 714+63-715+00 Rt.  
S.A.#2 717+34-717+58 Lt.

PROPERTY LINE FENCE WITH STEEL POSTS ITEM 585 II MOD		
STATION	STATION	POS
EASTBOUND		
1190+00	1204+50	EA
WESTBOUND		
1190+00	1205+00	EA

\* Const. "U" Turn  
EB 1201+50 Lt.

BRIDGE RAILING (FOR BRIDGE APPROACHES) ITEM 572		
STATION	STATION	POS
EASTBOUND		
1202+21.5	1204+50	EA
WESTBOUND		
1203+50	1204+50	EA

PILE MATTING ITEM 623		
STATION	STATION	POS
EASTBOUND		
1190+75	1193+00	EA

RIPRAP (LIGHT TYPE) ITEM 513-B		
STATION	STATION	POS
EASTBOUND		
1193+05	1194+00	EA

STONE FILL FOR SLOPE PROTECTION (LIGHT TYPE) ITEM 512		
STATION	STATION	POS
EASTBOUND		
1190+00	1197+00	EA

DEMOLITION AND DISPOSAL OF BUILDINGS ITEM 566	
STATION	POS
EASTBOUND	
1196+07	R+
1197+12	R+
WESTBOUND	
1197+50	LT
1198+27	LT

Wood Guide Posts  
S.A.# 715+40-716+63 Rt

Stage 2 Construction

STAGE 1 CONSTRUCTION

STATE OF VERMONT  
DEPARTMENT OF HIGHWAYS

RELOCATION OF U.S. ROUTE 4 IN THE TOWNS OF  
FAIR HAVEN - CASTLETON

PLAN  
STA. 1190+00.00 - 1205+00.00

WEBSTER-MARTIN, INC.  
CONSULTING ENGINEERS  
50 BURLINGTON, VERMONT

SCALE AS SHOWN

PROJECT NO. A P 020-1(20) SHEET 45 OF 421