



GUARD RAIL, STANDARD STEEL BEAM W/
STEEL POSTS, TYPE II, 6'-3" SPACING
EB 972+00 TO 972+78 RT.
EB 974+87 TO 987+00 RT.
WB 972+00 TO 972+28 LT.
WB 974+17 TO 987+00 LT.

APPROACH RAILING
EB 972+78 TO 973+05 RT.
EB 972+00 TO 973+00 RT.
EB 974+40 TO 974+67 RT.
EB 974+40 TO 975+32 LT.
WB 972+00 TO 972+55 RT.
WB 972+28 TO 972+55 LT.
WB 973+90 TO 974+17 LT.
WB 973+90 TO 976+15 RT.

WOVEN WIRE FENCE W/STEEL POSTS
WB 972+00 TO 972+55 LT.
EB 972+00 TO 973+05 RT.
EB 974+40 TO 988+00 RT.
WB 973+90 TO 988+00 LT.

TREATED TIMBER CURB
EB 972+00 TO 973+05 RT.
WB 972+00 TO 972+55 LT.
WB 973+90 TO 988+00 LT.
EB 974+40 TO 988+00 RT.

END LIMITED ACCESS
STA. BL 974+22
250' RT.

BEGIN LIMITED ACCESS
STA. BL 974+96
250' RT.

UNCLASSIFIED CHANNEL EXCAVATION
ITEM 203.27
WB 972+37 TO 975+00 LT.

STONE FILL, TYPE I, ITEM 618.10
WB 972+37 TO 973+00 LT.

COUNTERWEIGHT BERM
WB 972+00 TO 973+35 LT.
EB 972+00 TO 973+35 RT.

A 10' 15" LT.
D 0' 30"
R 11459.16
T 1027.74
L 2050.00
E 46.00
DO NOT BANK

PLAN SCALE
1" = 100 FEET

WEST RUTLAND - RUTLAND
SURVEYED BY: FALL DATE: JUNE 75
DRAWN BY: DZG DATE: JULY 75
TRACED BY: DZG DATE: JULY 75
PROJ. F NO. 020-1(11)
SHEET 43 OF 72