



STATE OF VERMONT
 AGENCY OF TRANSPORTATION
 (South Lot) to Town of Middlebury
 QCD 12/21/1988
 127/576

SWEY CURVE No. 1 DATA		REV. CURVE No. 1 DATA	
Δ	19° 29' 00" Lt	Δ	19° 29' 00" Lt
D	8' 00' 00"	D	2' 50' 00"
R	716.23'	R	2022.20'
T	23.36'	T	247.77'
L	243.54'	L	627.64'
E	10.48'	E	29.89'
		Bank	0.053 FvFt

See Dist Maint Deeds

TBM 3
 Top of Conc.
 Post
 Elev. 450.49

QUADRAL STANDARD STEEL BEAM WITH
 WOOD POSTS TYPE II ITEM 62125
 RIGHT
 REV 150+72 - REV 150+68
 LEFT
 REV 150+72 - REV 152+50
 CONSTRUCT DRIVE
 REV 154+01 RT (60' WIDE)

REMOVAL AND DISPOSAL OF
 EXISTING PAVEMENT VIA
 ITEM 203-15
 150+72 - 154+50
 NOTE: All removed bituminous
 material is to be salvaged and is
 to be stockpiled at the District
 5 maintenance yard on Creek Rd.
 in Middlebury.

DATUM
 VERTICAL: NGVD 1929
 HORIZONTAL: N.A.

CONSTRUCT SPECIAL DITCHING COMMON EXCAVATION ITEM 201-151
 REV 151+00 RT - REV 151+00 RT

SCALE IN FEET

MAY 23 1985

SURVEYED BY: MOSEAU DATE: 12/80
 DRAWN BY: MOSEAU DATE: MAY 85
 TRACED BY: 12/85 DATE: SEPT 85
 MIDDLEBURY
 PROJ. F 021-1(7)S
 SHEET 5 OF 6