



SURVEY  
U S 4  
CURVE DATA  
Δ 10° 08' LT.  
D 132.0'  
R 1273.2'  
T 132.0'  
L 263.0'  
E 6.8'  
BANK 0.63 X

NALETTE, WILFRED  
RIGHTS ACQUIRED BY W.D.E.  
DATED AUG. 28, 1981  
BOOK 94, PAGES 207-209

SURVEY  
U S 4  
CURVE DATA  
Δ 11° 50' LT.  
D 4° 30'  
R 1273.2'  
T 132.0'  
L 263.0'  
E 6.8'  
BANK 0.63 X

TH 6 15+50  
END APPROACH

TH 6 14+50 REV 14+45.81  
END CONSTRUCTION  
BEGIN APPROACH

QUECHEE LAKES CORP

BM # 2  
S.I.R. 36" ELM  
STUMP  
ELEV. 440.95'

END MAINT. AGREE. AREA NO. 2  
TH 6 14+79 CL

MAXWELL, ERNEST M. & TERRY-ANN  
MAXWELL, MARJORIE B.

US 4 449+20 =  
T.H. 132 11+49.81

SURVEY  
U S 4  
CURVE DATA  
Δ 14° 16.72'  
D 14° 16.46'

SURVEY  
U S 4  
CURVE DATA  
Δ 13° 13.84'  
D 13° 13.30'

SURVEY  
TH 6  
CURVE DATA  
Δ 12° 49' RT  
D 20'  
R 286.47'  
T 32.17'  
L 64.08'  
E 1.18'

453+00  
END CONSTRUCTION  
BEGIN APPROACH

454+00  
END APPROACH

SURVEY  
TH 6  
CURVE DATA  
Δ 9° 42' LT.  
D 7'  
R 816.51'  
T 139.57'  
L 2.94'

END MAINT. AGREE. AREA NO. 1  
TH 132 11+35 CL

SURVEY  
POST 451+04.0 =  
TH 6 POST 13+59.78  
Δ 116° 05' RT

SURVEY  
PI 13+04.59 =  
12+96.66

SURVEY  
TH 6  
CURVE DATA  
Δ 42° 13' LT.  
D 23° 30'  
R 224.68'  
T 96.74'  
L 165.55'  
E 15.16'

BEGIN MAINT. AGREE. AREA NO. 2  
TH 6 11+92 CL (252')

COURTEMANCHE, RAYMOND & BLANCHE  
END ROW. PROJECT  
STA. 454+40 CL

R.O.W. PLOTTED FROM PROJECT NRH 1086 OF 1934  
AREA IS PARCEL 25. LAND ACQUIRED BY WOODSTOCK  
R.R. FROM GILSON ETAL, BY COND. RECORDED IN BOOK  
22, PAGES 45 & 46.  
AREA LATER ACQUIRED BY ST. OF VT. FROM  
WOODSTOCK R.R., BY Q.C. DEED, OCT. 2, 1933 &  
RECORDED IN BOOK 46, PAGE 560

SURVEY  
PI 10+69.45 =  
10+69.12

TH 6 11+00  
BEGIN APPROACH

SR (P)  
CORNER OF CONST. EASE. (T)  
ELEV. 479.67'

REV. TH 6  
CURVE DATA  
Δ 29° 24' LT.  
D 15'  
R 381.97'  
T 100.21'  
L 196.00'  
E 12.93'

BEGIN MAINT. AGREE. AREA NO. 3  
TH 6 11+58 25' LT. (103')

CONSTRUCT DRIVE  
452+00 RT

REMOVAL AND DISPOSAL  
EXISTING GUARDRAILS  
449+00 ~ 450+72 LT  
447+00 ~ 449+38 RT  
450+12 ~ 450+60 RT  
451+48 ~ 451+16 LT  
451+40 ~ 451+64 RT

GUARDRAIL. STANDARD STEEL BEAM  
WITH WOOD POSTS TYPE II  
449+00 ~ 449+95 LT  
449+00 RT ~ 449+11+00 LT  
449+58 ~ 449+74 RT  
451+48 ~ 452+00 RT  
452+76 ~ 453+58 RT

WOOD GUARD POSTS (6" C-C)  
452+28 ~ 453+00 (ALONG  
LEFT SIDE OF DRIVE

STAGE II CONSTRUCTION

SURVEYED BY: FANTONI DATE: 8-78  
DRAWN BY: NEWHALL DATE: 10-78  
TRACED BY: NEWHALL DATE: 10-78

HARTFORD

PROJ. BRF NO. 020-2(17) S  
SHEET 8 OF 8

