

GENERAL NOTES (Continued from Sheet #1)

9. Turf Establishment Shall Be Considered Subsidiary To All Other Items In The Contract. See Special Provisions.
10. Traffic Will Not Be Allowed On The New Portions Of The Deck Until A Minimum Of 21 Days After Those Portions Of The Deck Have Been Poured, Or A Minimum Of 14 Days After Placement Of Concrete Curbs, Whichever Is Greater.
11. One Way Traffic Shall Be Maintained Over The Existing Bridge During Construction Under The Item 'Maintenance Of Traffic For Bridge Projects.' However, The One Way Traffic Will Be Controlled By Traffic Control Signals, Traffic Control Signals, Including Related Hardware, Equipment, And Incidentals Will Be Furnished, Installed And Maintained By State Forces. The State Shall Also Be Responsible For The Electric Power Required For The Operation Of The Signals. See Special Provisions.
12. Temporary Barrier Rail Shall Be Placed As Shown On Sheet - And Shall Be Paid Under The Item 'Temporary Barrier Rail.' See Special Provisions.

DATE	
BY	
REVISION	
NO.	
DESCRIPTION	
DATE	
BY	
REVISION	
NO.	
DESCRIPTION	
DATE	
BY	
REVISION	
NO.	
DESCRIPTION	

DATE	
BY	
REVISION	
NO.	
DESCRIPTION	
DATE	
BY	
REVISION	
NO.	
DESCRIPTION	

NOTE: FINISH GRADE PROFILE SHALL BE FIELD CHECKED AGAINST THE EXISTING BRIDGE DECK PROFILE, AFTER REMOVAL OF EXISTING PAVEMENT, TO INSURE PROPER DEPTH OF NEW PAVEMENT.

