DATUM
VERTICAL U.S.G.S.
HORIZONTAL VT. COORD. SYS.

PUB. RD. DIV. NO.	STATE	FED AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
1	VT.	HES-0109(2)	19		7

LIMIT OF CONSTR.
REV. STA. 7+50.00, 6.50' LT.
OF SURV. STA. 7 +50.00
BEGIN APPROACH

CONSTRUCT PAVED WALK
REV. 11+70 RT. (3.5' WIDE) (TO BE CONSTRUCTED IN A LOCATION MUTUALLY AGREEABLE W/ THE PROPERTY OWNER AND RESIDENT ENGINEER)

BEGIN PROJECT HES 0109(2)
REV. STA. 10+50.00, 3.76' RT.
OF SURV. STA. 10+49.99
END APPROACH

BEGIN R.O.W. PROJECT
HES 0109(2) REV. STA. 7+51 ℄

EROSION MATTING
LT. REV. STA. 15+80 ~ 18+50
RT. REV. STA. 13+00 ~ 13+50

REMOVAL & DISPOSAL OF GUIDE POSTS
℄ STA. 19+85 RT. ~ 21+00 RT.

REMOVAL & DISPOSAL OF GUARD RAIL
REV. STA. 13+25 RT. ~ 15+25 RT.
REV. STA. 17+05 RT. ~ ℄ STA. 18+75 RT.

STL. BEAM GUARD RAIL
REV. STA. 17+75 ~ ℄ STA. 21+00 RT.

CONSTRUCT DRIVE
LT. RT.
REV. STA. 8+20 (20' WIDE) REV. STA. 11+20 (14' WIDE)
REV. STA. 11+65 (14' WIDE)
REV. STA. 15+50 (14' WIDE)

EXCAVATION OF SURFACES & PAVEMENTS
REV. STA. 16+75 ~ ℄ STA. 19+25 RT.

SCARIFYING EXISTING PAV'T.
REV. STA. 12+75 ~ 18+25
℄ STA. 19+75 ~ 20+75

BREAKAWAY CABLE TERMINAL
REV. STA. 17+50 ~ 17+75 RT.

SURV. CURVE DATA #1
Δ = 8°10'00" LT.
D = 1°16'24"
R = 4500.00'
T = 321.25'
L = 641.41'
E = 11.45'

REV. CURVE DATA #1
Δ = 9°00'56" LT.
D = 1°16'24"
R = 4500.00'
T = 354.77'
L = 708.08'
E = 13.96'
BANK = 0.026 FT/FT

(BK) REV. STA. 17+80.48
(AH) SURV. STA. 17+80.16
EQ = +0.32'

SKIB, DONALD - ESTATE
ALLEN, ELEANOR A. - ADMINISTRATRIX

SKIBNIOWSKY, PETER JR.
& BEVERLY J.

TBM #1
SIT. 36" MAPLE
USGS EL. 306.96

TBM #2
SIT. 18" OAK
USGS EL. 299.27

SURV. POT 7+00.00

SURV. PC 11+38.75

SURV. PT. 17+80.16

SURV. PC 20+56.05

SCALE IN FEET
0 50 125 250

JUN 15 1995

11-02-92	REVISION 11

SURVEYED BY BRYANT/C.T. MALE DATE 7/85
DRAWN BY BRYANT ASSOC. DATE
TRACED BY DATE

VERNON
HES 0109(2)

R.O.W. SHEET 11 OF 14 SHEETS

6