

- NOTES:**
1. THESE PLANS SHOW A CONCEPTUAL EROSION CONTROL PLAN, THE CONTRACTOR MUST SUBMIT A TEMPORARY EPSC PLAN FOR APPROVAL.
 2. TEMPORARY EPSC PLAN MEASURES ARE CONCEPTUALLY SHOWN. THE CONTRACTOR MAY RELOCATE TEMPORARY MEASURES TO IMPROVE EROSION CONTROL WITH APPROVAL OF THE RESIDENT ENGINEER. SILT FENCE SHALL NOT BE INSTALLED ACROSS CONTOURS.
 3. THE CONTRACTOR SHALL USE OTHER TEMPORARY EROSION CONTROL MEASURES AS NECESSITATED BY THE SEQUENCE OF CONSTRUCTION OR AS DIRECTED BY THE RESIDENT ENGINEER.
 4. REFER TO TEMPORARY EROSION CONTROL DETAIL SHEETS FOR ADDITIONAL DETAILS.
 5. WHERE LEDGE IS EXPOSED, GRAVEL BAGS MAY BE USED INSTEAD OF FILTER CURTAIN. PAYMENT FOR THIS ITEM SHALL BE INCIDENTAL TO ITEM 649.61 "GEOTEXTILE FOR FILTER CURTAIN".

LEGEND


- EROSION MATTING
- LIMITS OF SOIL DISTURBANCE
- SILT FENCE
- PROJECT DEMARCATION FENCE
- BARRIER FENCE
- CHECK DAM
- FILTER CURTAIN
- STABILIZED CONSTRUCTION ENTRANCE
- AERIAL ELECTRIC & TELEPHONE
- RIPARIAN BUFFER ZONE
- APPROXIMATE SOIL BOUNDARY
- HISTORIC BUILDING

SOIL CLASSIFICATION

BERSHIRE-TUNBRIDGE COMPLEX (58D)
 15% TO 35% SLOPES
 "K FACTOR" = 0.32
 CLASSIFIED MODERATE EROSION POTENTIAL

COLTON FINE SANDY LOAM (64B)
 3% TO 8% SLOPES
 "K FACTOR" = 0.24
 CLASSIFIED MODERATE EROSION POTENTIAL

COLTON FINE SANDY LOAM (64C)
 8% TO 15% SLOPES
 "K FACTOR" = 0.24
 CLASSIFIED MODERATE EROSION POTENTIAL



PROJECT NAME: ROCHESTER
 PROJECT NUMBER: BRF 0162(17)

FILE NAME: r85e035.epsc.dgn
 PROJECT LEADER: J. FITCH
 DESIGNED BY: E.A. FIALA
 EPSC CONSTRUCTION CONDITIONS SHEET

PLOT DATE: 25-MAR-2013
 DRAWN BY: E.A. FIALA
 CHECKED BY: B.O. CRONIN
 SHEET 11 OF 12