QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

WATERBURY-STOWE F 029-1(12) NON-GOVT. PART. (WIDENING FOR BRN/JERSEY'S)	NON-FED PART.	ROADWAY	TOTAL	MORRISTOWN-WOLCOTT F 030-2(10) Non-Fed Part.		QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		3	3			3	EA	15" RCPES Cl III	601.6810	
		2	2		2	4	EA	18" RCPES Cl III	601.6815	
		3	3			3	EA	24" RCPES Cl III	601.6825	
		23(1 est)	23		13(1 Est.)	36	EA	Changing Elev. of DI, CB, or MH	604.40	
		7	7		7	14	EA	Cast Iron Grate w/Frame, Type A	604.45	
		16	16		4	20	EA	Cast Iron Grate w/Frame, Type B	604.46	
		1	1			1	EA	Cast Iron Grate w/Frame, Type E	604.52	
		2,000	2,000		1,000	3,000	LF	6" Underdrain (est)	605.10	
		200	200		100	300	LF	6" Underdrain Carrier Pipe (est)	605.20	
		10	10		5	15	Ea	Underdrain Flushing Basins (est)	605.95	
		250	250		125	375	HR	All Purpose Excavator Rental, Type I (est)	608.25	
		25	25			25	HR	All Purpose Excavator Rental, Type II (est)	608.26	
		75	75		35	110	HR	Power Broom Rental (est)	608.30	
		500	500		225	725	HR	Truck Rental (est)	608.37	
		20(8 est)	20		5(est)	25	CY	Stone Fill Type I	613.10	
		10(est)	10		65(15 est)	75	CY	Stone Fill Type II	613.11	
		75	75			75	LF	Cast in Place Cement Concrete Curb, Type B	616.28	
		1000(500 est)	1000		1000(500 est)	2000	LF	Treated Timber Curb	616.35	
		50	50		25	75	EA	Wood Marker Posts (est)	619.15	
		10	10		5	15	Ea	Removing & Resetting Property Markers (est)	619.20	
		15(7 est)	15		5(est)	20	Ea	Removing & Replacing Mailboxes	619.26	
	2000		2000	2000		4000	LF	Removing & Resetting Fence (est, Non-Fed)	620.50	
		7000(150 est)	7000		8500(287.5 est)	15,500	LF	Steel Beam Guard Rail	621.20	
					450	450	LF	Heavy Duty Steel Beam Guard Rail	621.21	
		17	17		30	47	EA	Breakaway Cable Terminal	621.50	
		23	23		6	29	EA	Anchor for Steel Beam Rail	621.60	
		750	750			750	LF	Removing & Resetting Guard Rail	621.75	
		5008	5008		6686	11,694	LF	Removal & Disposal of Guard Rail	621.80	
					60	60	LF	Temporary Traffic Barrier	621.90	
		875	875		350	1225	HR	Uniformed Traffic Officers (est)	630.10	
		1150	1150		475	1625	HR	Flaggers (est)	630.15	
		0.5	0.5		0.5	1	LS	Field Testing	631.15	
		0.7	0.7		0.3	1	LS	Mobilization	635.10	
100		350(est)	450			450	LF	Durable 4" White Line	646.30	
1450			1450			1450	LF	Durable 4" Yellow Line	646.34	
550			550			550	LF	Durable 8" Yellow Line	646.35	
20		80	100		36	136	LF	Durable 24" Stop Bar	646.40	
2		3(est)	5			5	EA	Durable Arrow Marking	646.42	
8		32	40			40	EA	Durable Letter in Word Marking	646.44	
		93,400	93,400		42,200	135,600	LF	Temporary 4" White Lines	646.50	
		153,600	153,600		64,400	218,000	LF	Temporary 4" Yellow Lines	646.51	
		180	180		80	260	CY	Topsoil (est)	651.35	
		1	1			1	EA	Deciduous Tree ~ European Mountain Ash (Sorbus Acuparia) B&B. 2" Cal	656.30	
18		610	628			628	SF	Traffic Signs, Type A	675.20	
75		2925	3,000			3,000	Lb	Flanged Channel Sign Posts	675.30	
		170	170			170	EA	Removing Signs	675.50	
		18	18			18	EA	Erecting Salvaged Signs	675.60	
		25	25			25	EA	Remove & Replace Reflector Units	676.15	
					1	1	EA	Traffic Control Signal System-Intersection (Mod)	678.15	
	160		160			160	SF	Travel Information Signs (Non-Fed.) (mod)	680.20	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

PROJECT NAME 1986 PAVING PROGRAM - DISTRICT 6
PROJECT NUMBER

SHEET 5 OF 108 SHEETS

D-1 JAN 95

BRUNING 65083