



FILE NAME IS: 1081201/STP/SSR; VIEW 6; BY: CMB; DATE: 10/05-12-11;

DATUM

VERTICAL	N/A
HORIZONTAL	N/A

CURVE	STATION	PC	PT	CC	RADIUS
1	111+89	27.7' LT	112+18	57.2' LT	111+89 57.7' LT 30.0'
2	112+18	64.9' LT	112+09	75.0' LT	112+09 65.0' LT 10.0'
3	112+88	27.5' LT	112+68	45.5' LT	112+90 57.5' LT 30.0'
4	112+63	45.5' LT	112+72	59.5' LT	112+72 49.5' LT 10.0'

- DURABLE 4" YELLOW LINE**
112+42 (2 SOLID LINES LT: DOUBLE CENTER LINE)
- DURABLE 24" STOP BAR**
112+12 TO 112+42 (1 SOLID LINE LT)
- DURABLE 4" WHITE LINE**
112+30 (1 SOLID LINE LT: SINGLE LANE LINE)
- DURABLE LETTER OR SYMBOL**
112+23 (5 SYMBOLS LT: RIGHT ARROW, O,N,L,Y)
112+36 (5 SYMBOLS LT: LEFT ARROW, O,N,L,Y)
- BITUMINOUS CONCRETE CURB**
111+89, 27.7' LT TO 111+88, 75.4' LT
112+63, 45.5' LT TO 112+90, 27.6' LT.
- CONCRETE CURB, TYPE B**
112+63, 45.5' LT TO 112+72 59.5' LT

Note: Signs shown on these plans are based upon signs as depicted by Project Berlin STP 9413 (1) 5 October 1994 submittal. Signs beyond the project limits of this project are to be modified per the revised 1994 STP plans supplied by VAOT.

LINES SHOWN ON THIS PLAN AS EXISTING PROPERTY LINES (P/L) ARE BELIEVED TO BE ACCURATE BUT SHOULD NOT BE RELIED UPON FOR PURPOSES UNRELATED TO THE STATE OF VERMONT'S ACQUISITION OF LAND AND RIGHTS FOR THIS PROJECT.

SIGN LEGEND

- R - REMOVE
- RET. - RETAIN
- R & S - REMOVE & SALVAGE
- S - SALVAGE
- N - NEW
- RP - REMOVE POST
- SP - SALVAGE POST
- NP - NEW POST

EXISTING	NEW	LEGEND
□	□	UTILITY POLE
○	○	LUMINAIRE
□	□	WOOD POLE
○	○	STRAIN POLE
□	□	CONTROLLER CABINET
□	□	PULLBOX/JUNCTION BOX
→	→	SIGNAL HEAD
△	△	VEHICLE LOOP DETECTOR
—	—	CONDUIT
—	—	VEHICLE LOOPS
●	●	PEDESTAL POST



SIGNING AND STRIPING PLANS

PREPARED BY	TAE/CMB	DATE	12/96
CHECKED BY	KGH	DATE	12/96
DESIGN SUPERVISOR	TAE	DATE	12/96
PROJ.	BERLIN		
	MG SGNL(4)		

R. O. W. SHEET 13 OF 17

FEB 19 2003 13