



**NEW GUARD RAIL - WORK SUMMARY**  
 CONSTRUCT NEW STEEL BEAM GUARD RAIL, ITEM 821.20 FROM 3+25 TO 8+25, 16' RIGHT OF ROUTE 108, 5'-8" LEFT OF SIDEWALK CENTERLINE, TO FACE OF RAIL. ADD TWO BREAKAWAY CABLE TERMINALS, ITEM 821.50, AT 3+00 TO 3+25, AND 8+25 TO 8+50. REMOVE EXISTING 2 CABLE WOOD POST GUARD RAIL FROM 2+92 TO 8+32 UNDER ITEM 821.80, REMOVAL AND DISPOSAL OF GUARD RAIL.

**IMPORTANT NOTE:**  
 THE 10' WIDE TEMPORARY CONSTRUCTION EASEMENT DOES NOT GIVE THE CONTRACTOR THE RIGHT TO DAMAGE TREES, BUILDINGS, SIGNS, WALKS, ETC. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES CAUSED IN THE COURSE OF CONSTRUCTION AND IS REQUIRED TO RESTORE THE PREMISES AS NEAR AS POSSIBLE TO THE CONDITION THEY WERE IN PRIOR TO CONSTRUCTION.

**IMPORTANT NOTE:**  
 IN CROSS-HATCHED AREAS THE CONTRACTOR SHALL LOWER THE EXISTING GRADE (BETWEEN THE BACK OF THE SIDEWALK AND THE EDGE OF ROUTE 108 BY 3" TO ALLOW EXISTING GRANULAR PATTERNS TO REMAIN WITH 4" OF BITUMINOUS CONCRETE SURFACING, ITEM 818.15 (TYPE B) TYPICAL. THROUGHOUT THE PROJECT THE CONTRACTOR SHALL PAID AS COMMON EXCAVATION FROM 203.18 SEE SHEET 8 FOR QUANTITIES

CONVENTIONAL SIGNS	
FENCE LINE	---
STONE WALL	○○○○○○○○○○
TED WAY	----
GUARD RAIL	----
SURVEY LINE	----
C	○
P	○
TREES (SOFTWOOD)	●
TREES (HARDWOOD)	○
PROPERTY LINE	----
TOP OF CUT	----
TOE OF SLOPE	----

**SITE PLAN**