

TRAFFIC SIGN SUMMARY

STATION	SIGN LEGEND	SIGN DIMENSIONS	NEW SIGNS SF	# OF POSTS	FLANGED CHANNEL LB/FT	REMARKS	PLAN SHEET #	STD SHEET #
0+32 LT		24 X 18	3.0	1	3	SEE DETAIL A ON ROUTE 100 SOUTHBOUND, NORTH OF DRIVE TO POLICE STATION	14	
		12 X 9	0.8			SEE DETAIL B BELOW PREVIOUS SIGN ON SAME POST	14	
0+27 RT		24 X 18	3.0	1	3	SEE DETAIL A FACING SOUTHBOUND TRAFFIC	14	
		24 X 24	4.0			SEE DETAIL D BELOW PREVIOUS SIGN ON SAME POST	14	
0+30 LT		18 X 18	2.3	1	3	SEE DETAIL G FACING NORTHBOUND TRAFFIC	14	
0+55 RT		12 X 18	1.5	1	3	SEE DETAIL C FACING SOUTHBOUND TRAFFIC	14	
0+80 LT		18 X 18	2.3	1	3	SEE DETAIL H FACING NORTHBOUND TRAFFIC	14	
1+30 LT		24 X 6	1.0	1	3	SEE DETAIL E FACING NORTHBOUND TRAFFIC	14	
		24 X 18	3.0			SEE DETAIL A BELOW PREVIOUS SIGN ON SAME POST	14	
8+00 LT		18 X 18	2.3	1	3	SEE DETAIL F FACING SOUTHBOUND TRAFFIC	14	
10+40 RT		24 X 6	1.0	1	3	SEE DETAIL E FACING SOUTHBOUND TRAFFIC	14	
		24 X 18	3.0			SEE DETAIL A BELOW PREVIOUS SIGN ON SAME POST	14	

STATION	SIGN LEGEND	SIGN DIMENSIONS	NEW SIGNS SF	# OF POSTS	FLANGED CHANNEL LB/FT	REMARKS	PLAN SHEET #	STD SHEET #
10+55 LT		18 X 18	2.3	1	3	SEE DETAIL F FACING NORTHBOUND TRAFFIC	14	
10+90 RT		18 X 18	2.3	1	3	SEE DETAIL H FACING SOUTHBOUND TRAFFIC	14	
10+80 LT		12 X 18	1.5	1	3	SEE DETAIL C FACING NORTHBOUND TRAFFIC	14	
11+28 LT		24 X 18	3.0	1	3	SEE DETAIL A FACING NORTHBOUND TRAFFIC	14	
		24 X 24	4.0			SEE DETAIL D BELOW PREVIOUS SIGN ON SAME POST	14	
11+40 RT		18 X 18	2.3	1	3	SEE DETAIL G FACING SOUTHBOUND TRAFFIC	14	
12+20 RT		24 X 18	3.0	1	3	SEE DETAIL A ON SOUTHSIDE OF RIVER ROAD-T.H.#5 75' EAST OF BRIDGE	14	
		12 X 9	0.8			SEE DETAIL B BELOW PREVIOUS SIGN ON SAME POST	14	
12+60 LT		24 X 18	3.0	1	3	SEE DETAIL A ON ROUTE 100 NORTHBOUND, ACROSS FROM RIVER ROAD INTERSECTION	14	
		12 X 9	0.8			SEE DETAIL B BELOW PREVIOUS SIGN ON SAME POST	14	

TOTAL SIGN AREA = 50.2 15 = TOTAL # OF POSTS
585 = TOTAL POUNDS

* THE POSTS LENGTHS ARE TO BE DETERMINED IN THE FIELD. FOR ESTIMATING PURPOSES 13' AVERAGE POST LENGTH WAS USED.
ALL SIGNS ARE TO BE A MINIMUM OF 8' CLEAR ABOVE THE GROUND SURFACE.

AUG 9 1994

PROJECT JUN 90 1992 BW-RS-BIKE (25)



TOWN OF STOWE - RIVER WALK
"TRAFFIC SIGN SUMMARY"

CHARLES GRENIER
CONSULTING ENGINEER, P.C.
BOX 445, WATERBURY, VERMONT
244-8413

DATE • 9-4-94
DRN BY • T.J.M.
SCALE • N/A
SHT 14 OF 20

14