STATE OF VERMONT

DEPARTMENT OF HIGHWAYS

PROPOSED IMPROVEMENT

INTERSTATE PROJECT

TOWNS OF SHARON--ROYALTON

COUNTY OF WINDSOR

INTERSTATE ROUTE 89

WHITE RIVER JCT.-MONTPELIER ROAD

BEGINNING AT A POINT 1.450 MILES SOUTHEAST OF THE SHARON-ROYALTON TOWN LINE AND EXTENDING NORTHWESTERLY 2.918 MILES

LENGTH OF ROADWAY 15,136.66 FEET = 2.867 MILES
LENGTH OF BRIDGES 289.51 FEET = 0.051 MILE

LENGTH OF PROJECT 15,406.17 FEET = 2.918 MILES

	DESIGN	DESIGNATION
ADT	1960	1500
ADT	1985	4175
DHV	1985	610
D		56%
T		8.5%
V		60 MPH



Dated

PERINI CORPORATION
73 MT. WAYTE AVENUE
FRAMINGHAM, MASS.

LOUIS A. CAMPANILE
VICE PRESIDENT
CONTRACTOR

Commissioner of Highways

END PROJECT I 89-1(36) — 775+93.04 — BEGIN PROJECT I 89-1(37)

END PROJECT I 89-1(37) — 936+00 — BEGIN PROJECT I 89-1(38) CONTRACT 1

SHARON — ROYALTON

CONVENTIONAL SIGNS

COUNTY LINE
TOWN LINE
RANGE LINE
STONE WALL
INTERCEPT PROPERTY
GUARD RAIL
TRAVELED WAY
RAILROAD
RETAINING WALL
CENTER LINE
SURVEY LINES
BENCHMARK
TOP POST
TRIANGULATION POLE
TELEPHONE POLE
TREES
TREE AND DIMENSION IDENTIFICATION

GROUND ELEVATION
GRADE ELEVATION

CURVE DATA
DEFLECTION ANGLE
DEGREE OF CURVE
RADIUS OF CURVE
TANGENT DISTANCE
LENGTH OF CURVE
EXTERNAL DISTANCE
POINT OF INTERSECTION
POINT OF CURVE
POINT OF TANGENT
POINT OF TANGENT
POINT OF SUB-TANGENT

LIMITED ACCESS

RIGHT-OF-WAY

SLOPE RIGHTS

TYPICAL CROSS SECTIONS
SCALE 10 FEET

NO RIGHT OF WAY DETAILS. SEE RIGHT OF WAY PLANS.

CONSTRUCTION TO BE CARRIED OUT IN ACCORDANCE WITH THESE PLANS AND THE STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION DATED APRIL 1964, AS AMENDED BY THE SUPERVISOR OF PUBLIC ROADS ON OCTOBER 14, 1964, INCLUDING ALL SUBSEQUENT UPDATES, REVISIONS AND SUCH PROVISIONS AND SPECIAL PROVISIONS AS ARE INCORPORATED IN THESE PLANS.

DEPARTMENT OF TRANSPORTATION
BUREAU OF PUBLIC ROADS

APPROVED
DIVISION ENGINEER
PROJECT I 89-1(37)
SHEET 1 OF 100 SHEETS

DATE
DATE
DATE
DATE

ROW I 89-1(17)
Sheet con
66