

DOPEDEY LINE FENCE W/
STEEL POSTS ITEM 533 II M-4
5' 00" - 14' 00" RT Ramp D

* STANDARD STEEL BEAM GUARD RAIL
W/STEEL POSTS ITEM 545-A (6" SPACING)
VT 107 29+00-30+55 LF

GRANITE SLOPE EDGING
ITEM 556-A
* 6+00 - 9+00 Ramp C RT
* 7+25 - 9+25 Ramp D LT
* 25+00 - 27+90 Island
* 28+54 - 32+00 Island
* 14+20 - 14+65 Ramp C LT
* 0+57 - 0+98 Ramp C LT
* 28+07 - 28+40 VT 107 LT

REMOVAL & DISPOSAL OF PRESENT GUARD
RAIL ITEM 549
VT 107, 25+00-27+90 RT
SPECIAL DITCH, ITEM 103
VT 107, 29+70-32+00 LT

* JUTE MATTING, ITEM 623
5' 00" - 14' 25" Lt Ramp D
THREE CABLE GUARD RAIL
W/STEEL POSTS ITEM 542
VT 107, 25+00-32+00 RT

BITUMINOUS CONCRETE SURFACE
TIE CUTTERS AND TRAFFIC ISLANDS
ITEM 554
VT 107, 29+60 RT
RAMPC 6+00 RT
RAMPD 5+25 RT

SUB-BASE OF SAND
ITEM 202
RAMPC 1+50-9+00
RAMPD 5+00-14+65
Δ 50° 41'
D 0"
E 726.20
T 339.10
L 633.54
E 76.22
Bank 3% per ft

GRAVEL BACKFILL FOR SLOPE
STABILIZATION ITEM 222-A
RAMPC 5+00-9+00 RT

Stone Fill Item 514
Ramp C 0+55-1+60 RT
Ramp D 17+25-18+60 RT
Ramp D 18+60-19+00 RT
Ramp D 19+00-20+00 RT

CONTROL OF ACCESS IS CONTROLLED ON THIS SHEET
EXCEPT AT STATION 0+18 RAMP "C"

Ramp D	Ramp C
Δ 43° 03' 22" Lt	Δ 167° 42' 51" Rt
D 1790.494'	D 22.9112'
Q 520 0'	Q 230.0'
T 128.25'	T 2137.01'
L 240.47'	L 673.25'
E 34.0'	E 1919.36'
bank 1% per ft	bank 1' per ft!

* DENOTES STAGE 2 CONSTRUCTION

RAMPS "C" & "D"

DEC 21 1973

STAGE 1 CONSTRUCTION

SURVEYED BY: _____ DATE: _____
DRAWN BY: J. Clark DATE: 12/21/73
TRACED BY: C. Clark DATE: 12/21/73
20' SCALE
37