



Three Cable Guard Rail Item 542
 N.B. 1582+00 Rt. - N.B. 1594+00 Lt.
 N.B. 1588+50 Lt. - N.B. 1592+00 Lt.
 S.B. 1585+00 Rt. - S.B. 1593+00 Rt.
 S.B. 1594+50 Lt. - S.B. 1598+00 Lt.

Stone Fill For Slope Protection Item 512
 N.B. 1588+98 - N.B. 1583+02 Lt.
 N.B. 1592+98 Lt. - N.B. 1593+02 Lt.
 N.B. 1596+98 Lt. - N.B. 1597+02 Lt.

Bituminous Concrete Curb Item 555
 N.E. 1589+00 Lt. - N.B. 1600+00 Lt.

Drilling & Blasting of Solid Rock Subgrade Item 115
 S.B. 1582+00 - S.B. 1583+25

N.B. Curve Data
 Δ 30° 39' 06" Lt.
 D 0° 30'
 R 11459.16
 T 3140.42
 L 6130.33
 E 423.50
 Bank 1/2" per foot.
 N.B. P.O.C. 1584+17.54

VERMONT DEPARTMENT OF HIGHWAYS
 RIGHT-OF-WAY PLANS
 Project: COYALTON-BETHEL-RANDOLPH
 No. 122-1(14)
 Sheet 28 of 50