



PLANK GUARD RAIL ITEM 340
SB 1943+73 Lt (16')
SB 1946+93 Lt (16')

* THREE CABLE GUARD RAIL WITH
LIGHT STEEL POSTS, ITEM 538
NB 1940+86'-1946+62' Lt
NB 1942+02'-1946+66' Lt
SB 1946+70'-1949+00' Lt
SB 1947+15'-1949+00' Lt
PROPERTY LINE FENCE
MOD ITEM 533-II
SB 1933+00'-1949+00'
NB 1933+00'-1949+00'
ML Fence to be erected prior to
Construction :-
1946+05'-1949+00' SB Lt.

* TREATED TIMBER CURB
ITEM 550
NB 1941+00'-1946+57' Lt
NB 1942+05'-1946+57' Lt
MUCK EXCAVATION, ITEM 117
NB 1943+50'-1946+00'

DRILLING AND BLASTING
OF SOLID ROCK SUBGRADE
ITEM 115
NB 1933+00'-1940+00'
SB 1933+00'-1940+00'
NB 1946+50'-1949+00'
SB 1946+50'-1949+00'

* = Stage 2 Construction.

B.M. 382 A
SB 1933+10 Rt.
30' Bee.
1465.57

B.M. 382
U.S. Elev.
1460.06
1458.02
NB 1933+50 Lt.
30' Bee.
1460.02

N.B. Curve Data
Δ 7°08'00" Lt ✓
D 0°15'00" ✓
R 22918.32 ✓
T 1428.57 ✓
L 2853.33 ✓
E 44.64 ✓
Do not bank ✓

B.M. 383
U.S. Elev.
1457.04
SB 1940+10 Rt.
12' M.
1463.54

B.M. 383
U.S. Elev.
1471.70
1471.05
SB 1944+50 Lt.
13' YB

B.M. 384
U.S. Elev.
1430.70

B.M. 384 A
U.S. Elev.
1426.04

Stage 2 Construction

RANDOLPH-BROOKFIELD
SURVEYED BY Fall DATE 6-64
DRAWN BY Buxton DATE 7-64
TRACED BY Ewell DATE 7-64
PROJ. I NO. 89-1 (28)
SHEET 69 OF SHEETS
Sheet 69 of 155 Sheets

Control of Access is complete on this Sheet.