



\* DENOTES STAGE 2 ITEMS

\* Standard Steel Beam Guard Rail  
w/ St. Posts (6'-3" Spacing)  
Item 545-A  
NB. 2054+51 - 2056+51.44 Lt.  
SB. 2055+48.27 - 2057+48.37 Rt.  
Note: Northbound Lane Standard  
Steel Beam Guard Rail Which  
Extends 49.00' into Project I-89-1(10)  
Shall be Constructed in its  
Entirety in this Contract.

\* Jute Matting  
Item 623  
2056+46 - 2060+00 Median  
2061+00 - 2063+00 Median  
2064+05 - 2065+50 Median  
2066+50 - 2070+00 Median

PROPERTY LINE FENCE W/STEEL POSTS  
ITEM 583-II MOD.  
N.B. 2066+96 - 2069+53 RT.  
(ERECT FENCE PRIOR TO COMMENCEMENT  
OF OTHER WORK IN THIS AREA.)  
S.B. 2055+57 - 2070+46 LT.

STA.	TA.	POS.
2056+41	2070+00	RT.
SOUTHBOUND		
2055+62	2070+00	LT.

N.B. & S.B. STA. 2055+00.00  
END PROJECT I-89-1(10)  
BEGIN PROJECT I-89-1(11)(29)  
CONTRACT No. 1

PORTER, O'BRIEN & ARMSTRONG  
CONSULTING ENGINEERS  
NEWARK, N.J.

NOTE:  
SEE SHEETS BR100 SERIES  
FOR THE ABOVE STRUCTURE  
FOR PLAN AND PROFILE OF  
BROOKFIELD STATE HIGHWAY  
SEE SHEET 25 OF 406

CONTROL OF ACCESS IS COMPLETE ON THIS SHEET

STAGE 1 CONSTRUCTION

BROOKFIELD-WILLIAMSTOWN  
BERLIN  
I 89-1 (11) (29)

CONTRACT No. 1

SHEET 28 OF 406  
263



73