



SB Curve Data
 Δ 17° 12' 40" LT
 D 2° 00'
 R 2864.79
 T 436.53
 L 866.20
 E 33.07
 bank 3/4 to 1/2

DRILLING & BLASTING OF SOLID
 ROCK, SUBGRADE, ITEM 115
 NB 162+00 - 169+00
 SB 162+50 - 169+00

SUB-BASE OF SAND, ITEM 202
 NB 153+00 - 157+00
 NB 153+50 - 162+00
 SB 153+50 - 162+00
 * TETD TRIPLE CURB, ITEM 538
 NB 156+25 - 161+00 LF
 SB 156+00 - 160+50 LF

* THREE CADLE GUARD
 2" x 11", ITEM 538
 SB 157+04 - 160+50 LF

PROPERTY LINE FENCE
 ITEM 503 II, MOD
 SB 153+00 - 169+00 LF
 NB 153+00 - 169+00 LF

* STD ST BEAM CP w/ ST POSTS
 ITEM 548-A (6'-3" Spacing)
 NB 153+00 - 163+00 LF

JUTE MATTING, IT 623
 SB 153+00 - 154+70 LF
 SB 155+70 - 156+12 LF
 SB 159+12 - 161+30 LF

* STAGE 3 FINISHED GRADES SHOWN
 STAGE 2 FINISHED ELEVATION 1 1/4 INCHES (0.1042 FT) BELOW
 STAGE 1 SUBGRADE ELEVATION 2.67 FEET
 (2 FT. 8 IN.) BELOW

STONE FILL, ITEM 512
 NB 153+00 - 161+00 LF
 SB 153+00 - 160+50 LF
 SB 160+50 - 162+50 LF
 NB 162+50 - 163+00 LF

CONTROL OF ACCESS IS COMPLETE ON THIS SHEET.

* DENOTES STAGE II ITEMS

SB 153+00 - 169+00 LF
 NB 160+00 - 164+00 LF
 Const. fence prior to commencement
 of other work in this area.

Approx. Aerial Reloc.
 Route by GMP Corp.

Cut to Fill Transition
 NB 156+25 - 157+00
 SB 160+30 - 161+00

STAGE 2 CONSTRUCTION
 BERLIN-MONTPELIER
 810
 160+00
 161+00

CONST.

54