



- CONST PLANK GUARD RAIL WITH PAINT - ROUTE 2 STA. 316+00 - 190' LT.
- DRILLING & BLASTING SOLID ROCK SUBGRADE ITEM 114 MOD. STA. 324+25 to 325+30 STA. 325+80 to 327+34 STA. 327+77 to 328+00
- THREE CABLE GUARD RAIL WITH STEEL POSTS STA. 313+00 to 313+40 WB RT. STA. 315+48 to 323+48 WB RT. STA. 314+39 to 326+55 E.B. LT.
- THREE CABLE GUARD RAIL WITH STEEL POSTS STA. 314+10 - 315+40 E.B. RT. STA. 314+38 - 323+40 E.B. RT. STA. 315+19 - 315+40 WB LT. STA. 315+50 - 317+85 WB RT.
- THREE CABLE MEDIUM GUARD RAIL AT BRIDGE STA 314+82' ✓
- EXCAVATION AND REMOVAL OF ROAD SURFACE ON ROADWAYS ITEM 118.A STA 316+00 to 328+00 LT.
- REMOVAL & DISPOSAL OF PRESENT GUARD RAIL ITEM 550 STA 315+86 to 326+60 LT.

Base Line Curve Data

A = 2°-33'
D = 07'-15"
R = 22918.32
T = 510.05
L = 1020.00
E = 568

Revised Base Line Curve Data

A = 2°-10'11"
D = 07'-15"
R = 22918.32
T = 433.33
E = 866.67
E = 410 - On Not Book

NOTE:
SEE SHEET NOS 63-66 FOR U.S. RTE.2 RELOCATION NO. 2

NOTE:
For Summary of Landscape Material Project I-89-2 (3) Sheet #32 Contract #4 Sheet #91

DRILLING & BLASTING SOLID ROCK SUBGRADE ITEM 114 MOD. STA. 324+44 to 325+23 STA. 325+60 to 326+65 STA. 327+0 to 328+78

PLAN AND PROFILE
STA 313+00 TO STA 328+00