PROPERTY LINE FENCE WITH STEEL POSTS
Left 637+83 to 638+00
642+25 to 642+50
641+50 to 644+50
Right 637+00 to 637+50
639+00 to 639+50
637+50 to 640+50

THREE CABLE GUARD RAIL WITH STEEL POSTS
Left 633+50 to 635+75
640+00 to 643+50
Right 641+50 to 642+50

LANDSCAPE MATERIAL
SHRUBS
632+00–638+50 RT. 10' continue
BLACK HAW. (71)
640+00–644+00 RT. 10'
BLACK HAW. (31)
TREES
637+25–638+00 RT. 100–110'
FLOWERING DOGWOOD (5)

51 J CENTRAL VERMONT RAILWAY, INC.
(A. 4.2±) STA. 634+66 – 679+00
RIGHTS TO DISCHARGE WATER FROM
11 CULVERTS – STA. 641+56 – 726+78
INTO 4 EXISTING RAILWAY CULVERTS. RIGHTS
TO DISCHARGE WATER FROM 9 CULVERTS –
STA. 636+91 – 683+21 INTO 3 RAILWAY
CULVERTS TO BE INSTALLED.
COND. 1/2/59
REC: WATERBURY – BK. 57 PG. 283–95 1/5/59

51 I CENTRAL VERMONT RAILWAY, INC.
(A. 0.20±) STA. 632+00 – 634+84
COND. 1/2/59
REC. MIDDLESEX – BK 27 – PG 436 1/5/59

54 CENTMONT CORP.

3 TOWN OF MIDDLESEX

5 – WARREN A. & CORA C. ROBY
(A. 27.0±) STA. 632+70 – 665+86±
CULVERT & DITCHING RTS. STA. 650+84
W. D. 12/24/58
REC.: WATERBURY BK. 57 PG. 235 12/29/58

39 BARNEY J. & ARLENE B. FISHER
(LOSS OF ACCESS) 60 ACRES±
STA. 644+70 – 652+00±
RELEASE 1/29/59
REC.: WATERBURY BK. 57 PG. 302 1/30/59

40 AZRO PERRY & GLEASON W. AYERS
(LOSS OF ACCESS) 135 ACRES±
STA. 644+00 – 652+00±
RELEASE 1/29/59
REC.: WATERBURY BK. 57 PG. 312 3/5/59

BEGIN FENCE
END FENCE
R.O.W. FENCE
TOWN LINE
CENTRAL VERMONT RAILROAD
BLACK HAW (68)
(34) BLACK HAW
FLOWERING DOGWOOD (5)
Clearing
Limit of Slopes
Boundary Marker TOWN LINE
Traverse Line
B.M. #102-A El. 489.03
B.M. #102-B El. 497.87
B.M. #103-C El. 482.20
B.M. #103-E El. 487.98

Note for Summary of Landscape Material
Project I-89-2(5) Sheet #24
Contract #1 Sheet #26

B.M. #102-A S.I.T. 15" Pine 120' Lt. Sta. 637+70 Elev. 489.03'.
B.M. #102-B S.I.T. 24" W. Birch 111' Lt. Sta. 635+50 Elev. 497.87'
B.M. #103-C S.O.L. 120' Lt. Sta. 645+60 Elev. 482.20'
B.M. #103-E S.O.L. 115' Lt. Sta. 640+10 Elev. 487.98'

STATE OF VERMONT
DEPARTMENT OF HIGHWAYS
INTERSTATE PROJECT IN THE TOWNS OF
MIDDLESEX — WATERBURY
PLAN
WILLIAM H. McFARLAND
ENGINEER
BINGHAMTON, N. Y.
SURVEYED BY
DRAWN BY
CHECKED BY
IN CHARGE
SCALE
DATE
PROJECT NO. I-89-2(5)
CONTRACT NO.
SHEET 40 OF 315

9