



THREE CABLE QUAD RAIL W/STEEL POSTS
 Left 663+96 Right 662+62
 660+00 to 663+96 660+00 to 662+62
 664+75 to 674+00 671+00 to 674+00
 665+00 667+00 to 674+00 (medium grade)

PROPERTY LINE FENCE W/STEEL POSTS
 668+00 Left 663+30 Right
 668+00 to 674+00 668+00 to 674+00
 667+00 to 674+00 668+00

LANDSCAPE MATERIAL TREES
 668+65 RT. 108' W. SPRUCE (1)
 668+75 RT. 110' W. PINE (1)
 668+90 RT. 100' W. SPRUCE (1)
 668+90 RT. 110' W. PINE (1)
 669+10 RT. 115' W. SPRUCE (1)
 670+65 RT. 100' W. PINE (1)
 670+65 RT. 90' W. PINE (1)
 670+80 RT. 110' W. PINE (1)

CURVE DATA - SURVEY B
 APC DEF
 P.I. 662+40.3 Bk. =
 662+32.34 Ahd.
 Δ = 14°34' RT.
 D = 113.01'
 E = 3019.72
 T = 356.10
 L = 1104.44
 SE = N 77°

CURVE DATA - RELOCATED E
 APC DEF
 P.I. 661+66.20 Bk. =
 661+56.44 Ahd.
 Δ = 14°34' RT.
 D = 113.01'
 E = 3019.72
 T = 356.10
 L = 1104.44
 SE = N 77°

B.M. 104-A S.T. 125' LI. Sta. 664+15 Elev. 470.96'
 S.T. 102 Oak
 Elev. 452-50 - 40' RT.

B.M. 104-A S.O.L. 125' LI. Sta. 664+15 Elev. 470.96'

B.M. 105-C S.T. 8" Pop 155' Rr. Sta. 666+25 Elev. 484.34'

Sta. 671+50 to Sta. 678+50
 Waterbury Refuse Area
 Unsuitable Material to be removed
 as indicated on Cross Sections Item
 101-C
 30% of this Material is to be made
 available for fill.

#6A VILLAGE OF WATERBURY
 (A 3450) STA. 665+53-704+221
 COND: 1/2/59
 RECORDED WATERBURY 1/5/59
 Bk 57 PG 283/98

Note: For Summary of Landscape Material
 Project 1-59-2153 Sheet #28
 Contract #1 Sheet #28

STATE OF VERMONT DEPARTMENT OF HIGHWAYS			
INTERSTATE PROJECT IN THE TOWNS OF MIDDLESEX - WATERBURY			
PLAN			
WILLIAM H. MCFARLAND ENGINEER BINGHAMTON, N.Y.			
SURVEYED BY	CHECKED BY	SCALE	DATE
DRAWN BY	IN CHARGE		
PROJECT NO. 1-59-2153	SHEET 44	OF 315	