Conveyed to Wesley A. Gokey QCD 3/21/63 Bk? Pg? 310

Relinquished #123

STEEL GUIDE POSTS
ITEM 548-B
LOCA. STA. STA. POS.
US-2 1140+00 1141+40 LT.

CONTRACT NO. 2
SOD REMOVAL
ITEM 101

LOCA	STA	STA	POS
	1141+00	1143+50	

1142+00 — 1142+72
3055 ADDITIONAL CY
BORROW FOR I-4 SLOPE AT
END OF CONTRACT # 2

CONTRACT NO. 2
1144 + 00 LT
END R.R. FRONTAGE ROAD
CONSTRUCT SATISFACTORY APPROACH

CONSTRUCT DRIVE

LOCA	STA	POS
US-2 REL	33+08	RT

SOD REMOVAL
ITEM 101

LOCA	STA	STA	POS
US-2 REL	1142+00	1143+50	RT

#100-C HENRY W. & HAZEL MARTELL
MEADOW
SLOPE RIGHTS - STA. 1141+00 - 1146+20±

#63-B SCOTT E. & RUTH E. DAYTON
(A.080±) STA 1148+40-1150+55±

#101 ARNOLD A. & VICTORIA G. MORSE
(A.161±) STA 1146+20-1148+62±

#122

#36-A STANLEY & THERESA STOCKWELL
(A.031±) STA 1143+06-1144+34±

END FENCE

BEGIN FENCE

#89-C TOWN OF BOLTON
(A.064±) STA 1150+00-1150+83±

#81-C PLANT & GRIFFITH LUMBER CO.
(A.062±) STA 1148+40-1150+20±

#14 SYDNEY SLAYTON
WATER PIPE STA 1150+50±

#4 GORDEN E. & JULIA CURTIS
(SQ. FT. 5002) STA 1150+50-1151+60±

HARLEY & HENRIETTA SHERMAN

BEGIN MAINT. AGREE. AREA NO. 1
U.S. 2 29+00 12' RT. (310')

END BRIDGE NO. 20 RESUME ROADWAY
1149 + 51.92

END MAINT. AGREE. AREA NO. 1
T.H. #10 3+10 ℄

END CONTRACT NO. 2 1142 + 00
BEGIN CONTRACT NO. 3

STOP ROADWAY 1145 + 43.50
BEGIN BRIDGE NO. 20
STOP ROADWAY U.S.-2 27+13.27
BEGIN BRIDGE NO. 19
END BRIDGE NO. 19 U.S.-2 28+03.35
RESUME ROADWAY

PROPERTY LINE FENCE
ITEM 563-B (MOD)
W/ STEEL POSTS

LOCA	STA	STA	POS
	1141+00	1142+00	LT

GATES FOR PROPERTY LINE FENCE ITEM 583-C

LOCA	STA	STA	POS

STONE FILL FOR SLOPE PROTECTION ITEM 522
BRIDGE NO. 19

LOCA	STA	STA	POS
US-2 REL	26+88	27+44	
"	27+75	28+20	

CONSTRUCT APPROACH

LOCA	STATION	POS
US-2 REL	29+00	RT

THREE CABLE GUARD RAIL WITH STEEL POSTS (ITEM 543)

LOCA	STA	STA	POS
LT. LANE	1142+00	1145+33	LT
"	1150+33	1151+69	LT
RT. LANE	1142+00	1145+33	RT
"	1149+04	1151+52	RT
US-2 REL	1142+00	1143+23	LT
"	26+29	27+01	LT
"	26+11	27+03	RT
"	28+11	28+99	LT
"	28+15	28+90	RT

IN MEDIAN AT BRIDGE APPROACHES

STATION
1149+51.92

PROPERTY LINE FENCE
ITEM 563-B (MOD)
W/ STEEL POSTS

LOCA	STA	STA	POS
	1164+49.6	1166+00	LT

DEMOLITION & REMOVAL OF BUILDING ITEM 586

BLDG. NO.	STATION	POS.
27	1143+65	LT
38	1145+0	LT
39	1145+25	RT
4	1145+50	LT
5	1145+35	RT
42	48+10	RT
43	1149+65	LT
44	37+90	RT. US-2

CONTRACT NO. 2

STATE HIGHWAY DEPARTMENT
DIVISION OF HIGHWAYS
INTERSTATE PROJECT
WATERBURY-BOLTON
PLAN
STA. 1140+00 TO 1156+00

WEBSTER WEFT INC.
CONSULTING ENGINEERS
SOUTH BURLINGTON, VT.

65

DESIGNED BY W.S.M. | DRAWN BY W.S.M. | CHECKED BY C.E.M. | DATE 9/14/59
PROJECT NO. BW-2-(7) | SHEET 65 OF 2

B.M. 56 SPOT ON HEADWALL 16" R.C.P. CULVERT 110' LT. STA. 1143+98 ELEV. 339.58

B.M. 57 SPOT ON CONC. STEP 22.8' RT. STA. 1149+79 ELEV. 356.60

SEP 6 1974

25