| FED. ROAD DIV. No. | STATE | FEDERAL PROJECT No. | SHEET | TOTAL SHEETS |
|---|---|---|---|---|
| 1 | VERMONT | I 89-3(14) | 3 | 160 |

PARCEL: 310
GRANTOR: ROLAND J & EVANGELINE S DESLAURIER, ET AL
STATIONS: 170+77 EB – 2045+35 ML
TAKING:
RIGHTS: SEWERAGE SYSTEM
TITLE TAKEN: COND 5/19/61
RECORDED: SO. BURLINGTON – BK. 63 – PG. 1 – 5/19/61

CHAIN LINK FENCE (ALUMINUM) ITEM 590-A (6'-0" HIGH)
STA. 2046+00 TO 2061+50 – ℄ P: 1546
STA. 2046+00 TO 2061+50 – ℄ LT: 576
3118

PAVED DITCH – ITEM 361-8
STA 2051+73 TO 2051+98 MEDIAN
STA 2058+23 TO 2058+48 "
STA 2058+52 TO 2058+77 "

PARCEL: 309
GRANTOR: LEO J. GIROUX, JR.
STATIONS:
TAKING:
REMAINDER:
RIGHTS: WATER PIPE LINE RIGHTS STA 2048+68

NOTE: *STAGE 2 ITEMS

PARCEL: 306
GRANTOR: CLEMENT E. & ARLENE J. COUILLARD
STATIONS: 2050+05 – 2053+48 BL
TAKING: 2.2 Ac
REMAINDER: 9.3 Ac
RIGHTS: NONE
TITLE TAKEN: COND 4/11/61
RECORDED: SO. BURLINGTON – BK. 48 – PG 453 – 4/11/61

PARCEL: 307 A,B
GRANTOR: UNIVERSITY OF VERMONT
STATIONS: 2053+43 – 2110+50 BL &
TAKING: 10.8 Ac
REMAINDER: 190.5 Ac
RIGHTS: CULVERT – STA. 2056+50, 2057+40
2059+00, 2067+50
2069+00, 2069+50
2073+90, 2077+00
TITLE TAKEN: PARCEL 'A' WD 4/17/61 PARCEL 'B' WD 4/17/61
RECORDED: SO. BURLINGTON-BK. 56-PG 364 – 5/18/61 SO. BURLINGTON-BK 56-PG 37 – 5/18/61

PARCEL: 307A
STATIONS: 2053+43 – 2078+07
TAKING: 9.8 Ac

EM. 180 Ac 2061+25 160' Rt (51 R 36" Elm) Elev. 298.64

RAMP "B" S 11°-03'-06.69" E
RAMP "D"
RAMP "D" CURVE DATA
Δ = 53°-38'-55.15"
D = 9°-46'-21.85"
R = 586.28' (Arc Def)
LL = 548.96'
T = 296.47'
Bank 1' per Ft.

INTERSTATE N 6°-41'-00" W
SOUTH BOUND
NORTH BOUND
CHAIN LINK FENCE
POWER LINE OVERHEAD CROSSING + 7 WIRES
CULTIVATED
WOODS (SCRUB BIRCH)
WOODS (SPRUCE, BEECH & PINE)
WOODS (SPRUCE & BEECH)
NEW HOUSES
PARCEL 304 B
PARCEL 306
PARCEL 307 A
JAMES E. & ELIZABETH JACOBS
CLEMENT E. & ARLENE J. COUILLARD
D. JAMES HILL
EVERETT M. & JANICE E. BUTTON
ROLAND J. & EVANGELINE S. DESLAURIER
MORRIS R. & ELIZABETH W. WILCOX
B.M. #180 EL. 306.34 S. T.
(OAKWOOD ROAD)
(GREENWOOD DRIVE)
(MELLOW DRIVE)
(HAZY ROAD)
DIRT ROAD
GRAVEL ROAD
EXISTING 6" SANITARY SEWER
CL. PIPE & SANITARY SEWER
SHEET 12
SHEET 14
MATCH LINE
321,000 E
321,500 E
713,500 N
714,000 N
714,500 N

Scale 1"=600'
Scale 1"=50'

Datum: Mean Sea Level 1929
500' Grid based on Vermont State Plane Coordinate System
Transverse Mercator Projection

NOTE:
FOR N.B. & S.B. PROFILE SEE SH. #18

I 89-3(16), I 189-3(17)
STAGE 2 CONSTRUCTION
SHEET 35 OF 167

STATE OF VERMONT
DEPARTMENT OF HIGHWAYS
INTERSTATE PROJECT IN THE TOWN OF SOUTH BURLINGTON.

PLAN
STA. 2046+00 TO STA. 2061+50

BOSWELL ENGINEERING CO.
CONSULTING ENGINEERS
ROSEFIELD PARK, N.J.

PROJECT NO. I-89-3(14) | SHEET 13 | OF 160

STAGE 1 CONTRACT 3

Const & ROW 22